

1 090380

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-171-20,300-000 *R*

SW SW NE, SEC. 35, T 18 S, R 31 *WEX*

2970 feet from S section line

2310 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5238

Lease Name Eitel 'E' Well # 1

Operator: Petroleum, Inc.

County Scott 154.05

Name & Address 300 W. Douglas, Suite 800

Well Total Depth 4740 Mississippi feet

Wichita, KS 67202

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 424

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X

Other well as hereinafter indicated _____

Plugging Contractor Cheyenne Drilling, Inc. License Number 5382

Address P. O. Box 916, Garden City, KS 67846

Company to plug at: Hour: 1:00 Day: 5 Month: August Year: 1985

Plugging proposal received from Phil Lloyd

(company name) Cheyenne (phone) 316-277-2062

were: to fill hole with heavy mud and spot cement through drill pipe Elevation 2966'
solid bridge Anhydrite N/A

1st plug at 2290' with 50 sx cement 5th plug hulls - plug at 40' -- cement to surface
with 10 sx cement

2nd plug at 1600' with 50 sx cement 7th plug to circulate rat hole with 15 sx cement

3rd plug at 1000' with 50 sx cement 8th plug to circulate mouse hole with 10 sx cement

4th plug at 450' with 40 sx cement

Plugging Proposal Received by Robert B. Tarbutton
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X

Operations Completed: Hour: 3:00 am Day: 5 Month: August Year: 1985

ACTUAL PLUGGING REPORT 1st plug at 2290' with 50 sx cement, 2nd plug at 1750' with 50

sx cement, 3rd plug at 1000' with 50 sx cement, 4th plug at 476' with 40 sx cement,

5th & 6th plugs - solid bridge - hulls - plug at 40' -- cement to surface with 10 sx

cement, 7th plug to circulate rat hole with 15 sx cement, 8th plug to circulate mouse

hole with 10 sx cement.

Remarks: Used 60/40 Pozmix 6% gel by Halliburton.

(If additional description is necessary, use BACK of this form.)

INVOICED

DATE 10-14-85

INV. NO. 10454
2-5

RECEIVED
STATE CORPORATION COMMISSION
Signed R B Tarbutton

OCT 14 1985

10-4-85

CONSERVATION DIVISION