

1 031346

8-29

API NUMBER 15-101-21,707-0000

To: STATE CORPORATION COMMISSION
Wichita State Office Bldg. PLUGGING SECTION
130 S. Market, Room 2078
Wichita, KS 67202

NW SW SW, SEC. 6, T 19 S, R 27 WXE
990 feet from S section line
330 feet from WXE section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 4767
Operator: Ritchie Exploration, Inc.
Name & Address: 125 N. Market, Ste. 1000
Wichita, KS 67202

Lease Name E. Shapland Trust Well # 6C #1
County Lane 150.80
Well Total Depth 4640 feet
Conductor Pipe: Size feet
Surface Casing: Size 8 5/8 feet 208

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X
Other well as hereinafter indicated _____

Plugging Contractor White & Ellis Drilling, Inc. License Number 5420
Address P.O. Box 48848, Wichita, KS 67201-8848

RECEIVED
STATE CORPORATION COMMISSION

Company to plug at: Hour: 7:30 a.m. Day: 29 Month: 8 AUG 30 1995

Plugging proposal received from Judy
(company name) White & Ellis Drilling, Inc.
Wichita, Kansas
(phone) 316-263-1102

Work: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 2097-2125'
1st plug at 2100' with 50 sx cement, 2nd plug at 1310' with 80 sx cement,
3rd plug at 810' with 40 sx cement, 4th plug at 230' with 40 sx cement,
5th plug at 40-0' with 10 sx cement,
6th plug to circulate rathole with 15 sx cement.

Plugging Proposal Received by Steve Durrant (TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X

Operations Completed: Hour: 9:30 a.m. Day: 29 Month: 8 Year: 1995

ACTUAL PLUGGING REPORT 1st plug at 2100' with 50 sx cement,
2nd plug at 1310' with 80 sx cement,
3rd plug at 810' with 40 sx cement,
4th plug at 230' with 40 sx cement,
5th plug at 40-0' with 10 sx cement,
6th plug to circulate rathole with 15 sx cement.

Remarks: Used 60/40 Pozmix 6% gel 1/4# floseal by Allied.
(if additional description is necessary, use BACK of this form.)

INVOICED

DATE 9-7-95
INV. NO. 43423

Signed Steve Durrant (TECHNICIAN)