

To: 1 080092  
STATE CORPORATION COMMISSION  
Wichita State Office Bldg. - PLUGGING SECTION  
130 S. Market, Room 2078  
Wichita, KS 67202

API NUMBER 15- 101-21,309-0000  
SW SW NE, SEC. 1, T 18 S, R 30 W/X  
2970 feet from S section line  
2310 feet from E section line

TECHNICIAN'S PLUGGING REPORT  
Operator License / 4629

Lease Name Sharp B Well / 1

Operator: Brito Oil Company, Inc.  
Name & Address 120 S. Market, Ste. 300  
Wichita, KS 67202

County Lane  
Well Total Depth 4590 149.17 feet  
Conductor Pipe: Size feet  
Surface Casing: Size 8 5/8 feet 298

Abandoned Oil Well X Gas Well Input Well SWD Well O&A

Other well as hereinafter indicated

Plugging Contractor Allied Cementing License Number

Address

Company to plug at: Hour: 10 a.m. Day: 18 Month: 12 Year: 19 96

Plugging proposal received from Raul F. Brito

(company name) Brito Oil Company, Inc. (phone) 316-283-8787

were: 4 1/2" at 4513' w/175 sx cement, PBSD 4436', Perfs at 4420-28, 4334-42', 200 sx ATL down  
1st plug pump 2 sx hulls and cement to 4340'. On 4/25/86, pumped 4 1/2" X 8 5/8" annulus

Check backside.

Plugging Proposal Received by Richard Lacey (TECHNICIAN)

Plugging Operations attended by Agent?: All X Part None

Operations Completed: Hour: 11:15 a.m. Day: 18 Month: 12 Year: 19 96

ACTUAL PLUGGING REPORT 1st plug pumped down 4 1/2" with 200 lbs. hulls and 220 sx cement.  
Maximum pressure 1200 psi and shut in 500 psi.

2nd plug pumped down 8 5/8" X 4 1/2" with 75 sx cement. No pressure. Cement stayed-didn't go on vacuum.

Remarks: Used 60/40 Pozmix 6% gel by Allied. No casing recovery.  
(if additional description is necessary, use BACK of this form.)

INVOICED  
DATE JAN 02 1997  
INV. NO. 47203

Signed Kevin D. [Signature] (TECHNICIAN)