

1 050823

231 P

To:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 101-21,319-0000
NW NW SE, SEC. 1, T 18 S, R 30 (W) X

TECHNICIAN'S PLUGGING REPORT

Operator License # 6113

Lease Name Sharp "B" Well # 1-1

Operator: Landmark Oil Exploration, Inc.

County Lane 147.65

Name & Address 105 South Broadway, Suite 1040

Well Total Depth 4543 feet

Wichita, KS 67202

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 263

Abandoned Oil Well Gas Well Input Well SWD Well D&A X

Other well as hereinafter indicated

Plugging Contractor H-30, Inc. License Number 5107

Address 251 North Water, Suite 10, Wichita, KS 67202

Company to plug at: Hour: 6:15 pm Day: 23 Month: June Year: 19 86

Plugging proposal received from Dick Davis

(company name) H-30 (phone) 316-263-2043

were: to fill hole with heavy mud and spot cement through drill pipe Elevation 2837' Anhydrite N/A

1st plug at the base of the Anhydrite with 50 sx cement

2nd plug at 1100' with 80 sx cement (1/2 Anhydrite + 300 ft.)

3rd plug 30' below the base of the surface pipe (290) with 40 sx cement

4th plug from 40' to surface with 10 sx cement

5th plug to circulate rat hole with 15 sx cement

Plugging Proposal Received by James R. Kapp

(TECHNICIAN)

Plugging Operations attended by Agent?: All X Part None

Operations Completed: Hour: 3:45 pm Day: 23 Month: June Year: 19 86

ACTUAL PLUGGING REPORT 1st plug at 2235' with 50 sx cement, 2nd plug at 1417' with 80

sx cement, 3rd plug at 290' with 40 sx cement, 4th plug from 40' to surface with 10

sx cement, 5th plug to circulate rat hole with 15 sx cement.

Remarks: Used 60/40 Pozmix 6% gel by BJ-Titan

(If additional description is necessary, use BACK of this form.)

INVOICED

DATE JUL 10 1986

INV. NO. 14321

STATE CORPORATION COMMISSION

7-8-86
JUL - 8 1986CONSERVATION DIVISION
Wichita, KansasSigned Richard W. Lacy
(TECHNICIAN)FORM CP-2/3
Rev. 01-84