

1050343

API NUMBER 15- 101-21,038-~~0000~~

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

W/2 SW NW, SEC. 6; T 18 S, R 30 W/X  
3300 feet from ~~XXX~~ SE Corner of section line  
4950 feet from ~~XXX~~ W SE Corner of section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5285

Lease Name Walter Well # 1

Operator: The Dane G. Hansen Trust

County Lane

Name & Address P. O. Box 187

Well Total Depth 3996 <sup>129.87</sup> feet

Logan, KS 67646

Conductor Pipe: Size            feet

Surface Casing: Size 8 5/8 feet 322

Abandoned Oil Well            Gas Well            Input Well            SWD Well            D&A X

Other well as hereinafter indicated           

Plugging Contractor Galloway Drilling Co., Inc. License Number 5783

Address 340 Broadway Plaza, 105 S. Broadway, Wichita, KS 67202

Company to plug at: Hour: 11:00 am Day: 12 Month: September Year: 19 84

Plugging proposal received from Paul McGuire

(company name) Galloway (phone) 316-263-1793

were:            to fill hole with heavy mud and spot cement through drill pipe

1st plug at 2290' with 50 sx cement

2nd plug at 1100' with 50 sx cement

3rd plug at 720' with 40 sx cement

4th plug at 360' with 40 sx cement

5th plug solid bridge Plugging Proposal Received by Richard W. Lacey  
hulls - plug at 40' -- cement to surface with 10 sx cement (TECHNICIAN)

7th plug to circulate rat hole with 10 sx cement

Plugging Operations attended by Agent?: All            Part            None X

Operations Completed: Hour: 1:30 pm Day: 12 Month: September Year: 19 84

ACTUAL PLUGGING REPORT 1st plug at 2290' with 50 sx cement, 2nd plug at 1100' with

50 sx cement, 3rd plug at 720' with 40 sx cement, 4th plug at 360' with 40 sx cement, 5th

& 6th plugs - solid bridge - hulls - plug at 40' -- cement to surface with 10 sx cement,

7th plug to circulate rat hole with 10 sx cement.

RECEIVED  
STATE CORPORATION COMMISSION

SEP 17 1984  
9-17-84

CONSERVATION DIVISION  
Wichita, Kansas

Remarks: Used 60/40 Pozmix 2% gel 3% cc by Allied.  
(If additional description is necessary, use BACK of this form.)

Signed Richard W. Lacey  
(TECHNICIAN)

**INVOICED**  
Contractor should observe this plugging.

DATE 9-21-84

INV. NO. 3837

9-12