

SEP 4 1987

API NUMBER 13- 101-21,411-0000

To: 1 030848
 STATE CORPORATION COMMISSION
 CONSERVATION DIVISION - PLUGGING SECTION
 200 COLORADO DERBY BUILDING
 WICHITA, KANSAS 67202

NE NE, SEC. 7, T 18 S, R 30 W

4610 feet from S section line

690 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5181

Lease Name Stormont "M" Well # 1

Operator: Donald C. Slawson

County Lane 150 44

Name &

Address 200 Douglas Building

Well Total Depth 4629 feet

Wichita, KS 67202

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 284

Abandoned Oil Well Gas Well Input Well SWD Well D&A X

Other well as hereinafter indicated

Plugging Contractor Slawson Drilling Company License Number 5657

Address Box 1409, Great Bend, KS 67530

Company to plug at: Hour: 11 a.m. Day: 4 Month: 9 Year: 19 87

Plugging proposal received from Bob Rowe

(company name) Slawson Drilling Company Inc. (phone) 316-793-3561

were: to fill hole with heavy mud and spot cement through drill pipe Elevation 2893' GL
Anhydrite 2259-80'

1st plug at Base Anhydrite with 50 sx cement, 2nd plug at 1530' with 80 sx cement,

3rd plug at 300' with 40 sx cement, 4th plug at 40-0' with 10 sx cement,

5th plug to circulate rathole with 15 sx cement.

Plugging Proposal Received by Steve Durrant
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None X

Operations Completed: Hour: 1:30 p.m. Day: 4 Month: 9 Year: 19 87

ACTUAL PLUGGING REPORT 1st plug at 2250' with 50 sx cement,

2nd plug at 1530' with 80 sx cement,

3rd plug at 300' with 40 sx cement,

4th plug at 40-0' with 10 sx cement,

5th plug to circulate rathole with 15 sx cement.

Remarks: Used 60/40 Pozmix 6% gel by Allied.

(If additional description is necessary, use BACK of this form.)

INVOICED (did not) observe this plugging.

Signed Steve Durrant
(TECHNICIAN)

DATE SEP 1 1 1987

INV. NO. 18086