

1 070535

MAY 10 1987

API NUMBER 15-101-21,380-0000

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

SE NW NW, SEC. 8, T 18 S, R 30 W/E

4290 feet from S section line

4290 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5614

Lease Name Ware Well # 1-8

Operator: Hutchinson Oil Company

County Lane 150.25

Name & Address: 105 South Broadway, Suite 470
Wichita, KS 67202

Well Total Depth 4623 feet

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 355

Abandoned Oil Well Gas Well Input Well SWD Well D&A X

Other well as hereinafter indicated

Plugging Contractor Warrior Drilling Company License Number 5883

Address 151 North Main, Suite 700, Wichita, KS 67202

Company to plug at: Hour: 7 p.m. Day: 10 Month: 5 Year: 1987

Plugging proposal received from Marion Burris

(company name) Warrior Drilling Company (phone) 316-262-3791

were: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 2274' Elevation 2895'

1st plug at Base Anhydrite with 50 sx cement, 2nd plug at Base Cheyenne with 80 sx cement,

3rd plug at 350' with 50 sx cement, 4th plug at 40' with 10 sx cement,

5th plug to circulate rathole with 15 sx cement,

6th plug to circulate mousehole with 10 sx cement.

Plugging Proposal Received by Steve Durrant (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None X

Operations Completed: Hour: 10 p.m. Day: 10 Month: 5 Year: 1987

ACTUAL PLUGGING REPORT 1st plug at 2274' with 50 sx cement,

2nd plug at 1500' with 80 sx cement,

3rd plug at 385' with 40 sx cement,

4th plug at 40' with 10 sx cement,

5th plug to circulate rathole with 15 sx cement,

6th plug to circulate mousehole with 10 sx cement.

Remarks: Used 60/40 Pozmix 6% gel by B.J. Titan. (if additional description is necessary, use BACK of this form.)

INVOICED

DATE 5-15-87

INV. NO. 16905

Signed Dan Jordan (TECHNICIAN)

RECEIVED STATE CORPORATION COMMISSION MAY 14 5-12-87 CONSERVATION DIVISION Wichita, Kansas