

To: 1 090755
STATE CORPORATION COMMISSION
Wichita State Office Bldg. - PLUGGING SECTION
130 S. Market, Room 2078
Wichita, KS 67202

API NUMBER 15- 101-21,730 - 6000

TECHNICIAN'S PLUGGING REPORT

11-3

NE SE SE, SEC. 10, T 18 S, R 30 W/X
1200 feet from S section line
400 feet from E section line

Operator License / 5393
Operator: A.L. Abercrombie, Inc.
Name & Address: 150 N. Main, Ste. 801
Wichita, KS 67202

Lease Name Huseman Well # 1
County Lane 150.96
Well Total Depth 4645 feet
Conductor Pipe: Size feet
Surface Casing: Size 8 5/8 feet 312

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ O&A X

Other well as hereinafter indicated _____

Plugging Contractor Abercrombie RTD, Inc. License Number 30684

Address 150 N. Main, Ste. 801, Wichita, KS 67202

Company to plug at: Hour: _____ Day: 3 Month: 11 Year: 19 96

Plugging proposal received from Tony

(company name) Abercrombie RTD, Inc. (phone) 316-262-1841

were: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 2234'

1st plug at 2240' with 50 sx cement, 2nd plug at 1450' with 80 sx cement,

3rd plug at 725' with 40 sx cement, 4th plug at 340' with 50 sx cement,

5th plug at 40' with 10 sx cement,

6th plug to circulate rathole with 15 sx cement.

Plugging Proposal Received by Steve Middleton (TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X

Operations Completed: Hour: 3 a.m. Day: 3 Month: 11 Year: 19 96

ACTUAL PLUGGING REPORT 1st plug at 2240' with 50 sx cement,

2nd plug at 1450' with 80 sx cement,

3rd plug at 725' with 40 sx cement,

4th plug at 340' with 50 sx cement,

5th plug at 40' with 10 sx cement,

6th plug to circulate rathole with 15 sx cement.

Remarks: Used 60/40 Pozmix 6% gel 1/4# flowseal by Allied.
(If additional description is necessary, use BACK of this form.)

INVOICED observe this plugging.

DATE NOV 13 1996
NO. 46942

Signed [Signature] (TECHNICIAN)