

To: 1 47758 6-24  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 101-21,655 ~~0000~~  
App. NW NW SW, SEC. 20, T 18 S, R 30 W/EK  
2163 feet from S section line  
515 feet from W/EK section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 31185  
Operator: B & T Oil Co.  
Name:  
Address 132 E. Long  
Dighton, KS 67839

Lease Name Shull Well # 1  
County Lane 149.66  
Well Total Depth 4605 feet  
Conductor Pipe: Size feet  
Surface Casing: Size 8 5/8 feet 332

Abandoned Oil Well Gas Well Input Well SWD Well D&A  
Other well as hereinafter indicated

Plugging Contractor Murfin Drilling Company, Inc. License Number 30606  
Address 250 N. Water, Ste. 300, Wichita, KS 67202

Company to plug at: Hour: Day: 24 Month: 6 Year: 19 93

Plugging proposal received from Rodney Farr  
(company name) Murfin Drilling Company, Inc. (phone) 316-267-3241

were: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 2197-2257  
1st plug at 2260' with 50 sx cement, 2nd plug at 1250' with 80 sx cement,  
3rd plug at 625' with 50 sx cement, 4th plug at 360' with 50 sx cement,  
5th plug at 40' with 10 sx cement, 6th plug to circulate rathole with 15 sx cement,  
7th plug to circulate mousehole with 10 sx cement.

Plugging Proposal Received by Steve Pfeifer (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None  
Operations Completed: Hour: 6:30 p.m. Day: 24 Month: 6 Year: 1993

ACTUAL PLUGGING REPORT 1st plug at 2260' with 50 sx cement,  
2nd plug at 1250' with 80 sx cement,  
3rd plug at 625' with 50 sx cement,  
4th plug at 360' with 50 sx cement, 5th plug at 40' with 10 sx cement,  
6th plug to circulate rathole with 15 sx cement,  
7th plug to circulate mousehole with 10 sx cement.

Remarks: Used 60/40 Pozmix 6% gel & # floseal by Allied  
(Additional description is necessary, use BACK of this form.)

INVOICED

(XXXX/ did not) observe this plugging.

DATE 7-7-93  
REV. NO. 38038  
6-24

Signed Stephen J. Pfeifer (TECHNICIAN)  
RECEIVED STATE CORPORATION COMMISSION JUN 30 1993  
CONSERVATION DIVISION Wichita, Kansas

SEP 15 1993