

1 030288

101-20,188-0000 *R*

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15 - Not Available

SE SW SE, SEC. 20, T 18 S, R 30 W/E
330 feet from N SE Corner of XXX section line
1650 feet from W SE Corner of XXX section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5131

Lease Name Shull Well # "A" 2

Operator: Thunderbird Drilling, Inc.

County _____ Lane _____

Name & Address P. O. Box 97

Well Total Depth 4613 *149.75* feet

Ellinwood, KS 67526

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 315

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling License Number 6050

Address Box 347, Chase, KS 67524

Company to plug at: Hour: 1:00 pm Day: 21 Month: September Year: 19 84

Plugging proposal received from Neil Peddicord

(company name) Kelso (phone) 316-938-2457

were: 4 1/2" set at 4553' PBD 4160' Perfs at 4130-36, 4268-92, 4305-12

1st plug sand back to 4055 and dump 4 sx cement on top of sand through bailer

2nd plug squeeze well with 2 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sack hulls, and 125 sx cement

Plugging Proposal Received by Steve Almont
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None

Operations Completed: Hour: 3:00 pm Day: 21 Month: September Year: 19 84

ACTUAL PLUGGING REPORT 4 1/2" set at 4553' PBD 4160' Perfs at 4130-36, 4268-92, 4305-12

1st plug sanded back to 4055' and dumped 4 sx cement on top of sand through bailer,

2nd plug squeezed well with 2 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sack hulls and 125 sx cement.

RECEIVED
STATE CORPORATION COMMISSION

OCT 09 1984
10-9-84

Remarks: Used 60/40 Pozmix 2% gel 3% cc
(if additional description is necessary, use BACK of this form.)

INVOICED

DATE 10-11-84

INV. NO. 4249

(if not) observe this plugging.

Signed Steve Almont
(TECHNICIAN)