

1050144

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION NE SW NW
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 101-20,875-0000
1850 feet from N ~~AS~~ section line
990 feet from W ~~AS~~ section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5254

Lease Name Sweeny Well # 1

Operator: Midco Exploration, Inc.

County Lane

Name & Address 411 Farmers & Bankers Bldg.

Well Total Depth 4660 151.45 feet

Wichita, KS 67202

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 344

Abandoned Oil Well Gas Well Input Well SWD Well D&A X

Other well as hereinafter indicated

Plugging Contractor Blue Goose Drilling License Number 5104

Address P. O. Box 1413, Great Bend, KS 67530

Company to plug at: Hour: 11:30 am Day: 13 Month: February Year: 19 84

Plugging proposal received from Leroy Boren

(company name) Blue Goose (phone) 316-792-5633

were: to fill hole with heavy mud and spot cement through drill pipe.

1st plug at 2200' with 50 sx cement

2nd plug at 1000' with 50 sx cement

3rd plug at 390' with 40 sx cement
solid bridge

4th plug hulls - plug at 40' -- cement to surface with 10 sx cement

6th plug to circulate rathole with 15 sx cement.

Plugging Proposal Received by Richard M. Lacy
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part X None

Operations Completed: Hour: 1:15 pm Day: 13 Month: February Year: 19 84

ACTUAL PLUGGING REPORT 1st plug at 220' with 50 sx cement, 2nd plug at 1000' with 50 sx

cement, 3rd plug at 390' with 40 sx cement, 4th & 5th plugs - solid bridge - hulls -

plug at 40' -- cement to surface with 10 sx cement, 6th plug to circulate rathole with

15 sx cement.

RECEIVED
STATE CORPORATION COMMISSION

FEB 22 1984

Remarks: Use 60/40 Pozmix with 2% gel 3% cc. by Sun Cement

(if additional description is necessary, use BACK WICHITA, KANSAS FORM.)

UNPLUGGED
(If additional description is necessary, use BACK WICHITA, KANSAS FORM.) observe this plugging.

DATE 2-23-84

Signed Richard M. Lacy
(TECHNICIAN)

INV. NO. 0346

2-13