

1 030864

9-30-87

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 101-21,420 - 07000

NW NW SW, SEC. 21, T 18 S, R 30 (W/R)

2320 feet from S section line

4950 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5181

Lease Name Steele "I" Well # 1

Operator: Donald C. Slawson

County Lane 150.15

Name

Address 200 Douglas Building

Well Total Depth 4620 feet

Wichita, KS 67202

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 278

Abandoned Oil Well Gas Well Input Well SWD Well D&A X

Other well as hereinafter indicated

Plugging Contractor Slawson Drilling Company License Number 5657

Address Box 1409, Great Bend, KS 67530

Company to plug at: Hour: 6 a.m. Day: 30 Month: 9 Year: 19 87

Plugging proposal received from Bob Rowe

(company name) Slawson Drilling Company (phone) 316-793-3561

were: to fill hole with heavy mud and spot cement through drill pipe Elevation 2887' Anhydrite 2225'

1st plug at 2250' with 50 sx cement, 2nd plug at 1470' with 80 sx cement,

3rd plug at 300' with 40 sx cement, 4th plug at 40-0' with 10 sx cement,

5th plug to circulate rathole with 15 sx cement.

Plugging Proposal Received by Steve Durrant (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None X

Operations Completed: Hour: 9:15 p.m. Day: 30 Month: 9 Year: 19 87

ACTUAL PLUGGING REPORT 1st plug at 2250' with 50 sx cement,

2nd plug at 1470' with 80 sx cement,

3rd plug at 300' with 40 sx cement,

4th plug at 40-0' with 10 sx cement,

5th plug to circulate rathole with 15 sx cement.

Remarks: Used 60/40 Pozmix 6% gel by Allied.

(If additional description is necessary, use BACK of this form.)

INVOICED
DATE 10-7-87
INV. NO. 18401

Signed Steve Durrant (TECHNICIAN)

RECEIVED
STATE CORPORATION COMMISSION
OCT 2 1987
10-2-87

09-30