

1050148

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-101-20,728-0000

SW NW NE, SEC. 18, T 18 S, R 29 W/4

1000 feet from N/4 section line

2310 feet from W/4E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5181

Lease Name Riley "W" Well # 1

Operator: Donald Slawson

County Lane

Name & Address 104 S. Broadway

Well Total Depth 4650 151.12 feet

Wichita, KS 67202

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 352

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Kelso Casing Pullers License Number 6050

Address Box 347, Chase, KS 67524

Company to plug at: Hour: 10:00 am Day: 13 Month: February Year: 19 84

Plugging proposal received from Bob Brenneman

(company name) Kelso Casing Pullers (phone) 316-938-8186

were: 4 1/2 set at 4649 Perfs 4364 - 68 PBTD 4590

1st plug sand back to 4300' with 4 sx cement dumped on top of sand

2nd plug squeeze head with 3 sx hulls, 15 sx gel, 70 sx cement, 15 sx gel, 1 sack hulls, and release 8 5/8" rubber plug and dump additional 130 sx cement.

Maximum pressure 800# and shut-in pressure 300#

Plugging Proposal Received by Richard M. Lacey  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 12:20 Day: 13 Month: February Year: 19 84

ACTUAL PLUGGING REPORT 4 1/2 set at 4649 Perfs 4364 - 68 PBTD 4590

1st plug sand back to 4300' with 4 sx cement dumped on top of sand

2nd plug squeeze head with 3 sx hulls, 15 sx gel, 70 sx cement, 15 sx gel, 1 sack hulls, and released 8 5/8" rubber plug and dumped additional 130 sx cement.

Maximum pressure 800# and shut-in pressure 300#

RECEIVED  
STATE CORPORATION COMMISSION  
2-22-84  
FEB 22 1984

Remarks: They recovered 2639 4 1/2. Use 60/40 Pozmix 2% gel 3% cc. by Allied  
(If additional description is necessary, use BACK of this form.)

**INVOICED**

I (did / did not) observe this plugging.

DATE 2-22-84

Signed Richard M. Lacey  
(TECHNICIAN)

INV. NO. 0309