

1 060929

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- N/A 101-20529-0000

C S/2 SE SW SEC. 25, T 18 S, R 29 W XX
330 feet from S section line
3300 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5393

Lease Name Hilgenberg Well # 3

Operator: A.L. Abercrombie, Inc.

County Lane 151.45

Name & Address 801 Union Center

Well Total Depth 4660 feet

Wichita, KS 67202

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 247

Abandoned Oil Well X Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Kelso Casing Pulling License Number 6050

Address Box 347, Chase, KS

Company to plug at: Hour: 3:15 p.m. Day: 9 Month: 1 Year: 19 87

Plugging proposal received from Ronny Hoover

(company name) Kelso Casing Pulling (phone) 316-938-2457

were: 4 1/2" at 4420' PBD 4300' Perfs at 4220-28' Elevation 2779'GL

1st plug sand back to 4170' and dump 4 sx cement on top of sand through bailer,

2nd plug shoot pipe at 1300', pump 150 sx cement,

3rd plug pump 150 sx cement down 8 5/8" annulus.

Plugging Proposal Received by Paul Luthi
(TECHNICIAN)

Plugging Operations attended by Agent?: All X Part None

Operations Completed: Hour: 1:30 p.m. Day: 14 Month: 1 Year: 19 87

ACTUAL PLUGGING REPORT 1st plug sanded back to 4170' and dumped 4 sx cement on top of sand through bailer, 2nd plug shot the 4 1/2" at 1306' and pumped 150 sx Econolite cement.

Went to pump 8 5/8" and it had hole in top of casing. Stopped at 6 p.m. on 1/9/87.

3rd plug started at 1 p.m. on 1/14/87 - pumped 150 sx cement (60/40 Pozmix 6% gel) down 8 5/8" annulus. Completed at 1:30 p.m. on 1/14/87.

Maximum pressure 200 psi and shut in 200 psi.

Remarks: Used Econolite and 60/40 Pozmix 6% gel by Allied.
(If additional description is necessary, use BACK of this form.)

STATE CORPORATION COMMISSION
1-16-87
JAN 16 1987
CONSERVATION DIVISION
Wichita, Kansas

INVOICED
Observe this plugging.

Signed Paul A. Luthi
(TECHNICIAN)

DATE 1-20-87

INV. NO. 15940