

To: 1 090278 4-30
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 101-20,842-0000118 R
W/2 W/2 SE, SEC. 35, T. 18 S, R. 29 W/EX

TECHNICIAN'S PLUGGING REPORT

Operator License # 5393
Operator: A.L. Abercrombie, Inc.
Name & Address
Rt. 1, Box 56
Great Bend, KS 67530

1320 feet from S section line
2210 feet from E section line
Lease Name Splitter B Well # 2
County Lane 151.77
Well Total Depth 4670 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 323

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____
Other well as hereinafter indicated _____

Plugging Contractor A.L. Abercrombie License Number 5393
Address Rt. 1, Box 56, Great Bend, KS 67530

Company to plug at: Hour: 1:10 p.m. Day: 30 Month: 4 Year: 19 93
Plugging proposal received from R.D. Rapp

(company name) A.L. Abercrombie (phone) 316-793-8186
were: 5 1/2" at 4667' w/225 sx cement, PBSD 4607', Port collar at 1684' w/450 sx cement
1st plug pump down 5 1/2" casing with 400 lbs. hulls and fill with cement.

Plugging Proposal Received by Steve Middleton
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____
Operations Completed: Hour: 1:50 p.m. Day: 30 Month: 4 Year: 19 93

ACTUAL PLUGGING REPORT 1st plug pumped down 5 1/2" casing with 400 lbs. hulls and 420 sx cement.
Maximum pressure 900 psi and shut in 350 psi.
Hooked onto backside, 300 lbs. pressure.

RECEIVED
STATE CORPORATION COMMISSION
5-5-93
MAY - 5 1993
RECEIVED
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
Wichita, Kansas
MAY - 5

Remarks: Used 60/40 Pozmix 6% gel by Allied. No casing recovery.
(If additional description is necessary, use BACK of this form.)

INVOICED
I () do / (X) do not observe this plugging.

DATE 5-12-93
INV. NO. 376.77
4-30

Signed 
(TECHNICIAN)