

1
050383

To:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 101-21,041 ~~0000~~

C N/2 S/2 SESEC. 36 ; T 18 S, R 29 W/K

990 feet from S section line

1320 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 9746

Lease Name D.E. Stanley Well # 1

Operator: Wilkar Oil Company

County Lane 152.43

Name & Address P. O. Box 3225

Well Total Depth 4690 feet

Santa Fe Springs, CA 90670

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 264 ✓

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X

Other well as hereinafter indicated _____

Plugging Contractor Blue Goose Drilling Co., Inc. License Number 5104

Address Box 1413, Great Bend, KS 67530

Company to plug at: Hour: 5:00 am Day: 14 Month: November Year: 19 84

Plugging proposal received from Leroy Boren

(company name) Blue Goose (phone) 316-792-5633

were: to fill hole with heavy mud and spot cement through drill pipe

1st plug at 2160' with 50 sx cement

2nd plug at 1110' with 50 sx cement

3rd plug at 720' with 40 sx cement

4th plug at 300' with 40 sx cement

5th plug solid bridge hulls - plug at 40' Plugging Proposal Received by Richard M. Lacey (TECHNICIAN) cement to surface with 10 sx cement

7th plug to circulate rat hole with 15 sx cement

Plugging Operations attended by Agent?: All _____ Part _____ None X

Operations Completed: Hour: 6:45 am Day: 16 Month: November Year: 19 84

ACTUAL PLUGGING REPORT 1st plug at 2160' with 50 sx cement, 2nd plug at 1110' with 50 sx cement, 3rd plug at 720' with 40 sx cement, 4th plug at 300' with 40 sx cement

5th & 6th plugs - solid bridge - hulls - plug at 40' -- cement to surface with 10 sx cement,

7th plug to circulate rat hole with 15 sx cement

RECEIVED
STATE CORPORATION COMMISSION
11-20-84
NOV 20 1984

Remarks: Used 60/40 Pozmix 2% gel 3% cc by Halliburton. (If additional description is necessary, use BACK of this form.)

CONSERVATION DIVISION
Wichita, Kansas

INVOICED (did not) observe this plugging.

Signed Richard M. Lacey (TECHNICIAN)

DATE 12-4-84

INV. NO. 5791 16-16 JAN 14 1985