

15-171-30064-0000

Form CP-3  
Rev. 6-26-62

KANSAS

*W*  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION

AUG 29 1966  
8-29-66  
CONSERVATION DIVISION  
WICHITA, KANSAS

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita 2, Kansas

Operator's Full Name Katex Oil Company.

Complete Address: 1604 South Cedar, Borger, Texas.

Lease Name Eitel Well No. 1-25

Location SE-SE-NW Sec. 25 Twp. 18 Rge. (E) (N) 31

County Scott Total Depth 2823

Abandoned Oil Well      Gas Well      Input Well      SWD Well      D & A X

Other well as hereafter indicated:     

Plugging Contractor: Murfin Drilling Company.

Address: 617 Union Center, Wichita, Kansas. License No.     

Operation Completed: Hour 8:30AM Day 26 Month 8 Year 1966

The Above well was plugged as follows:

246'--8 5/8" Surface pipe, cement circulated with 185 Sx.  
Circulated hole with heavy mud, set plug @ 600' and displaced 25 Sx.  
cement thru DP. Heavy mud to 240', set plug and displaced 20 Sx. cement  
thru DP. Heavy mud to 30', set plug with 1/2 sack hulls and 10 Sx. cement  
to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: A. D. Fichel  
Well Plugging Supervisor

DATE 8/29/66  
INV. NO. 3833-4