

KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

RECEIVED
STATE CORPORATION COMMISSION
JUL 1 1963
7-1-63
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Underwriters Oil Corporation,

Complete Address: 300 Weber Building, Lake Charles, Louisiana.

Lease Name Chance Well No. 1

Location NE-NW-NW Sec. 30 Twp. 18 Rge. (E) (W) 31

County Scott Total Depth 4015

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated: _____

Plugging Contractor: National Drilling Company, Inc.,

Address: 533 Petroleum Building, Wichita, KS License No. _____

Operation Completed: Hour 1000AM Day 24 Month 6 Year 1963

The Above well was plugged as follows:

255' --8 5/8" Surface pipe, cement circulated.

Circulated hole with heavy mud, set plug @ 540' and displaced 20 Sx cement thru DP. Heavy mud to 250', set plug and 1/4 sack hulls and displaced 20 Sx cement thru DP. Heavy mud to 40', set plug and 1/2 sk hulls and 10 sx cement to bottom of cellar.

(Mr. Quattlebaum of National Drilling Company Inc., asked that they be billed for the plugging fee.)

I hereby certify that the above well was plugged as herein stated.

Signed: H. L. Dehals
Well Plugging Supervisor