

15-101-00068-0000

Form CP-3
Rev. 6-26-62

KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

NOV 30 1964
11-30-64
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name Graybol Oil Corporation,
Complete Address: 2200 NBT Building, Tulsa, Oklahoma.
Lease Name Whipple Well No. 1
Location CNE-SE Sec. 15 Twp. 19 Rge. (E) (W) 27
County Lane Total Depth 4700
Abandoned Oil Well Gas Well Input Well SWD Well D & A X
Other well as hereafter indicated:
Plugging Contractor: Above
Address: License No.

Operation Completed: Hour 9:00AM Day 25 Month 11 Year 1964

The Above well was plugged as follows:

252'--8 5/8" Surface pipe, cement circulated with 165 Sx.
Circulated hole with heavy mud, set plug @ 540' and displaced 20 Sx.
cement thru DP. Heavy mud to 240', set plug with 1/2 sack hulls and dis-
placed 20 Sx. cement thru DP. Heavy mud to 40', set plug with 1/2 sack
hulls and 10 Sx. cement to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 12/2/64
INV. NO. 259-11

Signed: M. L. Nichols
Well Plugging Supervisor