

15/01-20069-0000

Form CP-3
Rev. 6-4-68

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

RECEIVED
STATE CORPORATION COMMISSION
NOV 26 1973
11-26-73
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Thunderbird Drilling, Incorporated,

Complete Address Box #18107, Wichita, Kansas.

Lease Name Pinkston Well No. A-1

Location NW-SW-NE Sec. 4 Twp. 18 Rge. (E) (W) 29

County Lane Total Depth 4600'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated

Plugging Contractor Red Tiger Drilling Company,

Address 1720 Wichita Plaza, Wichita, Ks. License No.

Operation Completed: Hour 5:30 PM Day 17 Month 11 Year 1973

The above well was plugged as follows:

453'--8 5/8" Surface casing, cement circulated with 250 Sx.
Top of Dakota section @ 350'.

Circulated hole with heavy mud. Pulled DP to 600' and displaced 90 Sx. cement thru
DP from 600' to 325'. Pulled DP, set bridge @ 10' with 1/2 sack hulls and 10 Sx. cement
to bottom of cellar.

INVOICED
I hereby certify that the above well was plugged as herein stated.

DATE 11/29/73
INV. NO. 8218-W

Signed: W. L. D. [Signature]
Well Plugging Supervisor