

STATE OF KANSAS
KANSAS CORPORATION COMMISSION
CONSERVATION DIVISION
130 South Market - Room 2078
Wichita, Kansas 67202

FORM CP-1 (3/92)

WELL PLUGGING APPLICATION FORM
(PLEASE TYPE FORM and File ONE Copy)

API # 15-101-20,182 ⁰⁰⁰⁰ (Identifier number of this well). This must be listed for wells drilled since 1967; if no API# was issued, indicate spud or completion date.

WELL OPERATOR Whitetail Crude, Inc KCC LICENSE # 31627 ^{2/02}
(owner/company name) (operator's)

ADDRESS P O Box 544 CITY Ness City

STATE KS ZIP CODE 67560-0544 CONTACT PHONE # () 785-798-3641

LEASE Cowdery WELL# 2 SEC. 29 T. 18S R. 30W ~~XXXX~~ West

NW - NW - NE SPOT LOCATION/QQQQ COUNTY Lane

330 FEET (in exact footage) FROM X/N (circle one) LINE OF SECTION (NOT Lease Line)

330 FEET (in exact footage) FROM X/W (circle one) LINE OF SECTION (NOT Lease Line)

Check One: OIL WELL GAS WELL D&A SWD/EMHR WELL DOCKET# _____

CONDUCTOR CASING SIZE _____ SET AT _____ CEMENTED WITH _____ SACKS

SURFACE CASING SIZE 8 5/8 SET AT 302 CEMENTED WITH 200 SACKS

PRODUCTION CASING SIZE 4 1/2 SET AT 4453 CEMENTED WITH 150 SACKS

LIST (ALL) PERFORATIONS and BRIDGEPLUG SETS: 4270-90, 4303-06, 4352-55, 4123-32

ELEVATION 2891 T.D. 4600 PBTD _____ ANHYDRITE DEPTH _____
~~XXXXX~~ K.B. (Stone Corral Formation)

CONDITION OF WELL: GOOD POOR CASING LEAK JUNK IN HOLE

PROPOSED METHOD OF PLUGGING Sand off perts, spot 4 sks w/dump bailer, shoot off 4 1/2 @

1200'. Pull 1 jt, pump 80 sks of 60x46, pull 4 1/2 to 600' & pump 40 sks. Pull 4 1/2 to

300', pump 50 sks, pull 4 1/2 out, top off 8 5/8" with 10 sks. Job complete.

(If additional space is needed attach separate page)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? yes IS ACO-1 FILED? unknown

If not explain why? _____

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et. seq. AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

LIST NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

Mike J. Fritzler, President Whitetail Crude, Inc PHONE# () 785-798-3641

ADDRESS P O Box 544 City/State Ness City, KS 67560-0544

PLUGGING CONTRACTOR Swift Services, Inc KCC LICENSE # 32382 ^{10/02}
(company name) (contractor's)

ADDRESS P O Box 466, Ness City, KS 67560-0466 PHONE # () 785-798-2300

PROPOSED DATE AND HOUR OF PLUGGING (If Known?) ASAP 1-2-2002 @ 10:25 am plugged

PAYMENT OF THE PLUGGING FEE (K.A.R. 82-3-118) WILL BE GUARANTEED BY OPERATOR OR AGENT

DATE: 12/26/01 AUTHORIZED OPERATOR/AGENT: Mike J. Fritzler
Mike J. Fritzler, President

RECEIVED
DEC 31 2001
12-31-01
WICHITA