

API NUMBER 15-101-20,154-00-00  
LEASE NAME Cowdery  
WELL NUMBER #1  
990 Ft. from N Section Line  
990 / 1050 Ft. from WE Section Line

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE OPERATOR Whitetail Crude, Inc  
ADDRESS P O Box 544, Ness City, KS 67560-0544  
PHONE # (785) 798-3641 OPERATORS LICENSE NO. 31627

SEC. 29 TWP. 18S RGE. 30W (E) or (W)  
COUNTY Lane  
Date Well Completed 8/75  
Plugging Commenced 5/10/01  
Plugging Completed 5/10/01

Character of Well oil  
(Oil, Gas, D&A, SWD, Input, Water Supply Well)  
The plugging proposal was approved on 5/9/01 (date)  
by Kevin Strube (KCC District Agent's Name).

Is ACO-1 filed? unknown If not, is well log attached?  
Producing Formation Marmaton Depth to Top 4266-86 Bottom 4346-48  
4302-04 4363-73 T.D. 5600 4100

Show depth and thickness of all water, oil and gas formations.

**RECEIVED**

OIL, GAS OR WATER RECORDS | CASING RECORD | KANSAS CORPORATION COMMISSION

Formation	Content	From	To	Size	Put in	Pulled out
				8 5/8	327	
				4 1/2	4436	537

6-11-01  
JUN 11 2001

CONSERVATION DIVISION

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each section. Sanded off perfs to 4200' & spotted 4 sks of cement through a dump bailer. Shot perforation holes @ 1208'. Mixed 100 sks & displaced to 648'. Shot casing off @ 537', lifted pipe up & pumped a 50 sk plug. Pulled pipe to 40', circulated and pumped 20 sks, laid down last joint & topped off 8 5/8". Job complete.

Name of Plugging Contractor Swift Services, Inc License No. \_\_\_\_\_

Address P O Box 466, Ness City, KS 67560-0466


NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Whitetail Crude, Inc

STATE OF Kansas COUNTY OF Ness, ss.

Mike J. Fritzler, President of Whitetail Crude, Inc (Employee of Operator) or (Operator)  
above-described well, being first duly sworn on oath, says: That I have knowledge of the facts  
statements, and matters herein contained and the log of the above-described well as filed to  
the same are true and correct, so help me God.

(Signature) Mike J. Fritzler

(Address) P O Box 544, Ness City, KS 67560-0544



SUBSCRIBED AND SWORN TO before me this 8th day of June, 2001, KX

Debra Kerr  
Debra Kerr Notary Public

My Commission Expires: 4/20/2005

USE ONLY ONE SIDE OF EACH FORM

01

29-18-30W  
SE NW NE

THUNDERBIRD DRILG. INC. #1 COWDERY

P.O. BOX 18407, WICHITA, KS.

CONTRACT NO. 10015 CTY. LANE

SEOL. FIELD COWDERY DLSC.

+	+
+	+
+	+

2894-KB c/w 8/4/75 CARD ISSUED 9/25/75 P 70 BOPD + 30 BWPD

HARM 4363-73

15-101-20,154

LOG TOPS	DEPTH	DATUM	
			B 5/8" 327/175SX, 4 1/2" 4436/100SX
ANH A	2183	+ 711	DST (1) 3968-4000/60", 10'M, SIP 1081-
HEEB	3891	- 997	1170 1073#/30", FP 35-52#
TDR	3908	-1014	DST (2) 4125-50/75", 2400'SO&GCSW, SIP
LANS	3935	-1041	X 1194-1185#/60", FP 744-779#
BKC 4274	4214	-1420	DST (3) 4150-70/60", 2500'MW, SIP 1194-
MARM	4328	-1434	1185#/45", FP 986-1055#
PAW	4392	-1498	DST (4) 4333-50/30", 10'M, W/SPKS O, SIP
FT SC	4442	-1548	X 1038-920#/ FP 35-52#
CHER	4458	-1564	DST (5) 4357-4385/30-45-45-80, REC 2100'
MISS	4530	-1636	G 400'CO, 1290'MO, 90'HOCSSW, SIP 865-
LTD	4597	-1703	900#, FP 555-727#, (GR 340)
RTD	4600	-1706	DST (6) 4397-4425/60", 2'M, SIP 173-173#/
			30", FP 35-52#
			DST (7) 4436-70/60", 20'O SPK M, SIP 1055-
			986#/30", FP 43-69#

INDEPENDENT OIL & GAS SERVICE  
WICHITA, KANSAS

M/S

(CONT)

15-101-20154-0000