

STATE CORPORATION COMMISSION  
130 S. Market, Room 2078  
Wichita, KS 67202

K.A.R.-82-3-117

API NUMBER 15-101-20182-00-00

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE NAME Cowdery

WELL NUMBER #2

330 Ft. from <sup>N</sup> Section Line

330 Ft. from <sup>W</sup> Section Line

SEC. 29 TWP. 18S RGE. 30W (X) or (W)

COUNTY Lane

Date Well Completed 7/9/76

Plugging Commenced 12/28/01

Plugging Completed 1/2/02

LEASE OPERATOR Whitetail Crude, Inc

ADDRESS P O Box 544, Ness City, KS 67560

PHONE/(785) 798-3641 OPERATORS LICENSE NO. 31627

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 12/26/01 (date)

by Mike Maier (KCC District Agent's Name).

Is ACO-1 filed? unknown if not, Is well log attached? sent with CP-1

Producing Formation Kansas City Depth to Top \_\_\_\_\_ Bottom \_\_\_\_\_ T.D. 4600

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				4 1/2	4453	558

RECEIVED  
FEB - 4 2002  
KCC WICHITA

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet each section.  
12/28/01 Sanded off perfts to 3200' & capped with 4 sks thru a dump bailer. 1/2/02 Perforated pipe @ 1300' & pump. Mixed 80 sks of 60x40 6% gel & 300# of hulls in the last 40 sks & displaced to 800'. Shot casing off @ 558'. pulled it & pumped 40 sks & displaced to 520'. PULLED casing to 300' & pumped 50 sks to 300'. Pulled casing out & topped off 8 5/8" to surface. Job complete.


Name of Plugging Contractor Swift Service, Inc License No. \_\_\_\_\_

Address P.O Box 466, Ness City, KS 67560

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Whitetail Crude, Inc

STATE OF Kansas COUNTY OF Ness, ss.

Mike J. Fritzler, President of Whitetail Crude, Inc (Employee of Operator) or (Operator) above-described well, being first duly sworn on oath, says: That I have knowledge of the facts and statements, and matters herein contained and the log of the above-described well as filed in the same are true and correct, so help me God.



(Signature) Mike J. Fritzler

(Address) P O Box 544, Ness City, KS 67560-0544

SUBSCRIBED AND SWORN TO before me this 14th day of January, 2002

Debra Kerr  
Debra Kerr Notary Public

My Commission Expires: 4/20/05

USE ONLY ONE SIDE OF EACH FORM

OR