

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-101-21,177-0000

LEASE NAME Delmar Whiting

WELL NUMBER 1

SPOT LOCATION SE SW SE

SEC. 31 TWP. 18 RGE. 30 (E) or (W)

COUNTY Lane

Date Well Completed 6-23-85

Plugging Commenced 6-23-85

Plugging Completed 6-23-85

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Osborn Heirs Co.

ADDRESS P. O. Box 17968, San Antonio, TX 78286

PHONE # (512)826-0700 OPERATORS LICENSE NO. 5249

Character of Well D & A
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? District 1

Is ACO-1 filed? No If not, is well log attached? Yes

Producing formation N/A Depth to top _____ bottom _____ T.D. 4640

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size 8 5/8	Put in 218	Pulled out None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from _____ feet to _____ feet each set.

Spotted 50 sx Cement @ 2250' thru drill pipe
Spotted 70 sx cement @ 810' thru drill pipe
Spotted 40 sx cement @ 240' thru drill pipe
Spotted 10 sx cement @ 40' thru drill pipe
Spotted 15 sx cement in rathole

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor White & Ellis Drilling, Inc. License No. 5420

Address 401 East Douglas, Suite 500, Wichita, Ks. 67202

STATE OF Kansas COUNTY OF Sedgwick, ss.

Ernest Sifford (employee of operator) or (operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Ernest Sifford

(Address) 401 E. Douglas, Suite 500
Wichita, Ks. 67202


SUBSCRIBED AND SWORN TO before me this 12th day of July, 19 85

DAVID F. JAMIS
NOTARY PUBLIC
STATE OF KANSAS
My Comm. Exp. 6-10-87

David F. Jamis
Notary Public

RECEIVED
CORPORATION COMMISSION
My Commission expires: _____

7-15-85
CONSERVATION DIVISION



31-18-30W
SE 8WSE

WHITE

AND ELLIS DRILLING, INC.

15-101-21177-0000

DRILLERS LOG

OPERATOR: Osborn Heirs Co.
 Box 17968
 San Antonio, TX 78286

CONTRACTOR: White & Ellis Drilling, Inc., 401 E. Douglas, Suite 500,
 Wichita, Ks. 67202

Lease Name Delmar Whiting Well No. 1

Sec. 31 T. 18S R. 30W Spot SE SW SE

County Lane State Kansas Elevation _____

Casing Record:

Surface: 8 5/8" @ 218' with 2% gel.
38cc 135 sx.

Production: _____ @ _____ with _____ sx.

Type Well: D & A Total Depth 4640

Drilling Commenced 6-12-85 Drilling Completed 6-23-85

Formation	From	To	Tops
Cellar	0	7	
Sand	7	218	
Shale, Lime	218	902	
Sand, Lime	902	1706	
Sand, Shale	1706	2336	
Lime, Shale	2336	4190	
Lime, Shale, Sand	4190	4220	
Lime, Shale	4220	4640	

1-17-87
 JUN 19 1987
 CONSERVATION DIVISION
 WICHITA, KANSAS

JUL 16 1985

State Geological Survey
 WICHITA BRANCH

K. G. S. LIBRARY