

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-101-20997-0000

LEASE NAME McKenna

WELL NUMBER 1

SPOT LOCATION SE NE SW

SEC. 10 TWP. 18 SRGE. 29 (N) or (W)

COUNTY Lane

Date Well Completed 7/25/84

Plugging Commenced 7/25/84

Plugging Completed 7/25/84

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR PETRO-DYNAMICS CORPORATION

ADDRESS 555 n. Woodlawn Ste 207, Wichita, KS 67202

PHONE # (316) 681-1685 OPERATORS LICENSE NO. 5053

Character of Well D&A
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Dodge City, KS

Is ACO-1 filed? Yes If not, is well log attached? _____

Producing formation _____ Depth to top _____ bottom _____ T.D. 4675

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				6 jts. 8	5/8 " 24#	@ 263' KB None

Describe in detail the manner in which the well was plugged, indicating where the mud-fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set. Cemented w/210 sx 60-40 Pozmix 2% Gel, 3% CaCl2

1st plug @ 2170' w/50 sx
2nd plug @ 1110' w/50 sx
3rd plug @ 690' w/40 sx
4th plug @ 300' w/40 sx 10 sx in Rathole
5th plug @ 40' w/10 sx 10 sx in Mousehole

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Allied Cementing License No. _____

Address P.O. Box 678, Great Bend, KS 67530

STATE OF Kansas COUNTY OF Sedgwick, ss.

Lincoln M. McGinnis (XXXXXXXXXXXXXXXXXXXX) or
(operator) of above-described well, being first duly sworn on oath, says: That
I have knowledge of the facts, statements, and matters herein contained and
the log of the above-described well as presented that the same are true and
correct, so help me God.

STATE CORPORATION COMMISSION

(Signature) Lincoln M. McGinnis


(Address) _____

AUG 02 1984

8-2-84

SUBSCRIBED AND SWORN TO before me this 1 day of August, 1984
Wichita, Kansas

Suzanne P. Graef
Notary Public



My Commission expires: Oct. 26, 1985