

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-101-21,380-0000

LEASE NAME WARE

WELL NUMBER 1-8

SPOT LOCATION SE NW NW

SEC. 8 TWP. 18 RGE. 30 ~~CRK(W)~~

COUNTY Lane

Date Well Completed 5-10-87

Plugging Commenced 5-10-87

Plugging Completed 5-10-87

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR HUTCHINSON OIL CO.
ADDRESS 105 S. Broadway Suite 470 Wichita, Ks. 67202

PHONE # (316) 262-1525 OPERATORS LICENSE NO. 5614

Character of Well D & A
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? yes

Which KCC/KDHE Joint Office did you notify? District #1

Is ACO-1 filled? yes If not, is well log attached? yes

Producing formation NA Depth to top NA bottom T.D. 4623'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
Surface	8 5/8" 8 jts set @	353		cem w/	200 sks	60-40 posmix

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set.
Plugged w/50 sks @ 2274', 80 sks @ 1500', 40 sks @ 385', 10 sks @ 40', 15 sks RH, 10 sks MH, started @ 7:00 pm, Comp. @ 10:00 pm
Dan Goodrow District #1 State Plugger

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Warrior Drilling Co. Rig # 2 License No. 5883
Address 151 N. Main #700 Wichita, Ks. 67202

STATE OF Kansas COUNTY OF Sedgwick, ss.

MAY 29 1987
5-29-87

~~XXXXXXXXXX~~ F.W. Shelton, Jr. (employee of operator) or
above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) F.W. Shelton, Jr.

(Address) 905 Century Plaza, Wichita, Ks. 67202

MARTHA E. GUSTIN
NOTARY PUBLIC
STATE OF KANSAS
MY APPL. EXPIRES 11-15-87

SUBSCRIBED AND SWORN TO before me this 11 day of May, 19 87

Martha E. Gustin
Notary Public
Notary Public

My Commission expires: _____

NOTICE OF INTENTION TO DRILL

(see rules on reverse side)

Starting Date 4 30 1987
month day year

API Number 15- 101-21,380-0000

OPERATOR: License # 5614
 Name Hutchinson Oil Co.
 Address 105 S. Broadway, Suite 470
 City/State/Zip Wichita, Kansas 67202
 Contact Person Steve Hutchinson
 Phone 316 262 1525

SE NW NW Sec. 8 Twp. 18 S, Rg. 30 East
4290 West
4290 West
 Ft. from South Line of Section
 Ft. from East Line of Section

(Note: Locate well on Section Plat on reverse side)

CONTRACTOR: License # 5883
 Name Warrior Drilling Co.
 City/State Wichita, Kansas 67202
 Well Drilled For: Oil SWD Infield Mud Rotary
 Gas Inj Pool Ext. Air Rotary
 OWWO Expl Wildcat Cable

Nearest lease or unit boundary line 990 feet
 County Lane
 Lease Name Ware Well # 1-8
 Ground surface elevation 2895 feet MSL
 Domestic well within 330 feet yes no
 Municipal well within one mile yes no
 Depth to bottom of fresh water 104
 Depth to bottom of usable water 1560
 Surface pipe by Alternate: 1
 Surface pipe planned to be set 320'
 Conductor pipe required -0-
 Projected Total Depth 4550 feet
 Formation Mississippian

If OWWO: old well info as follows:
 Operator
 Well Name
 Comp Date Old Total Depth

I certify that well will comply with K.S.A. 55-101, et seq., plus eventually plugging hole to KCC specifications.
 Date 4/22/87 Signature of Operator or Agent William J. Hutchinson Title Owner

For KCC Use:
 Conductor Pipe Required 215 feet; Minimum Surface Pipe Required 215 feet per Alt. P.P.
 This Authorization Expires 10-23-87 Approved By 4-23-87 [Signature]

Spud 5-2-87
Set 320' [Signature]

SE NW NW Sec. 8 Twp. 18 S, Rg. 30 East
4290 West

PLUGGING PROPOSAL IF ABOVE IS D & A

This plugging proposal will be reviewed and approved or revised at the time the district office is called prior to setting surface casing (call 7 a.m. to 5 p.m. workdays).

1st plug @ <u>Base Anhu</u> feet depth with <u>50</u> size of <u>60/140 poz. mix 68 gel</u>
2nd plug @ <u>Base Cheyene</u> feet depth with <u>80</u> size of <u>60/140 poz. mix 68 gel</u>
3rd plug @ <u>350</u> feet depth with <u>50</u> size of <u>60/140 poz. mix 68 gel</u>
4th plug @ <u>90</u> feet depth with <u>10</u> size of <u>60/140 poz. mix 68 gel</u>
5th plug @ <u>15</u> feet depth with <u>10</u> size of <u>60/140 poz. mix 68 gel</u>
(2) Rathole with <u>15</u> size
(b) Mousehole with <u>10</u> size

PUSHER Moran Buis
 TD 4623' FORMATION MISS.
 SURFACE PIPE 8 5/8" @ 355'
 ANHYDRITE 2274' ELEVATION 2895'
 STARTING TIME & DATE 7:00 PM 5-10-87
 COMPLETION TIME & DATE 10:00 PM 5-10-87
 1st PLUG @ 2274 FT. W/ 50 SX
 2nd PLUG @ 1500 FT. W/ 80 SX
 3rd PLUG @ 385 FT. W/ 40 SX
 4th PLUG @ 40 FT. W/ 10 SX
60/140 poz. 68 gel
 RAT HOLE CIRCULATED W/ 15 SX
 MOUSE HOLE CIRCULATED W/ 10 SX
~~WATER WELL PLUGGED W/ 10 SX~~
 CEMENT COMPANY B.J. Titan
 TECHNICIAN D.G. saw nose

RECEIVED
 STATE CORPORATION COMMISSION

MAY 11 1987
5-12-87
 CONSERVATION DIVISION
 Wichita, Kansas