

STATE OF KANSAS
 KANSAS CORPORATION COMMISSION
 CONSERVATION DIVISION
 30 South Market - Room 2078
 Wichita, Ks. 67202

WELL PLUGGING RECORD
 K.A.R.-62-3-117

15-101-21730-00-00

API NUMBER 15-101-20,703-000

LEASE NAME Huseman

WELL NUMBER 1

1200 Ft. from S Section Line

400 Ft. from E Section Line

SEC. 10 TWP. 18 RGE. 30 (E) or (W)

COUNTY Lane

Date Well Completed 11-03-96

Plugging Commenced 11-03-96

Plugging Completed 11-03-96

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

LEASE OPERATOR A.L. Abercrombie, Inc.

ADDRESS 1150 No. Main, Ste 801, Wichita, Ks. 67202

PHONE# (316) 262-1841 OPERATORS LICENSE NO. 5393

Character of Well D/A

(Oil, Gas, O&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on _____ (date)

by _____ (KCC District Agent's Name).

Is ACQ-1 filed? Enclosed If not, is well log attached? _____

Producing Formation _____ Depth to Top _____ Bottom _____ T. _____

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
Surface				8 5/8"		None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet each set.
 Fill with heavy mud. 1st plug from 2240'-2040' with 50 sks. 2nd plug from 1450'-1130' with 80 sks. 3rd plug from 725'-545' with 40 sks. 4th plug from 340'-140' with 50 sks. 5th plug from 40'-0' with 10 sks. 15 sks cathole.
 total 245 sks.

Name of Plugging Contractor Abercrombie RTD, Inc. License No. 30684

Address 150 N. Main, Ste 801, Wichita, Ks. 67202

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: A.L. Abercrombie, Inc.

STATE OF Kansas COUNTY OF Sedgwick, ss.

Jerry L. Langrehr (Employee of Operator) or (Operator)
 above-described well, being first duly sworn on oath, says: That I have knowledge of the fact statements, and matters herein contained and the log of the above-described well as filed in the same are true and correct, so help me God.

(Signature) Jerry L. Langrehr

(Address) _____

SUSANRA COMAND SWORN TO before me this 18th day of December, 19 96
 NOTARY PUBLIC
 STATE OF KANSAS
 My Appl. Exp. 1-2-98
Sandra C. McCraig
 Notary Public

My Commission Expires: 1-31-98

USE ONLY ONE SIDE OF EACH FORM

RECEIVED
 KANSAS CORP. COMM
 1996 DEC 19 A 11:27

EFFECTIVE DATE: 10-2-96

State of Kansas

101-21,730

FORM MUST BE TYPED

DISTRICT # 1

NOTICE OF INTENTION TO DRILL

FORM MUST BE SIGNED

SCA? Yes No

Must be approved by the K.C.C. five (5) days prior to commencing well.

ALL BLANKS MUST BE FILLED

Expected Spud Date 10/01/96 month day year

Spot 165 N of NE-SE SE Sec 10 Twp 18 S Rg 30 East West

OPERATOR: License # 5393 Name: A.L. Abercrombie, Inc. Address: 150 No. Main, Suite 801 City/State/Zip: Wichita, Ks. 67202 Contact Person: Jerry Langrebe Phone: 316-262-1841

1155 1200 feet from South / XXXX line of Section 330 400 feet from East / XXXX line of Section IS SECTION XX REGULAR IRREGULAR?

(NOTE: Locate well on the Section Plat on Reverse Side) County: Lane

CONTRACTOR: License #: 30684 Name: Abercrombie RTD, Inc.

Lease Name: Huseman Well #: 1 Field Name: Wildcat

Is this a Prorated/Spaced Field? yes XX no Target Formation(s): LKC

Well Drilled For: Well Class: Type Equipment: XX Oil Enh Rec Infield XX Mud Rotary Gas Storage Pool Ext. Air Rotary CWWD Disposal XX Wildcat Cable Seismic; # of Holes Other

Nearest lease or unit boundary: 330 Ground Surface Elevation: 2862 est feet MSL

Water well within one-quarter mile: yes XX no Public water supply well within one mile: yes XX no

If CWWD: old well information as follows: Operator: Well Name: Comp. Date: Old Total Depth

Depth to bottom of fresh water: 100-180 Depth to bottom of usable water: 1450

Surface Pipe by Alternate: 1 XX 2 Length of Surface Pipe Planned to be set: 300

Length of Conductor pipe required: N/A Projected Total Depth: 4600

Formation at Total Depth: MJsalsippj Water Source for Drilling Operations: well farm pond XX other

Directional, Deviated or Horizontal wellbore? yes XX no If yes, true vertical depth: Bottom Hole Location:

Will Cores Be Taken? yes XX no If yes, proposed zone:

200' Alt. II Req.

Exp. 3/27/97

AFFIDAVIT

The undersigned hereby affirms that the drilling, completion and eventual plugging of this well will comply with K.S.A. 55-101, et. seq.

Pusher Tony SPUD DATE 10/25/96 INIT. [Signature] LENGTH SURFACE PLANNED 3007 RESERVE PIT STATUS- REMOVE FLUID LINED after salt sect. bbls. when done bbls. RATHOLED AHEAD? Y N SIZE HOLE SURFACE PIPE 8 1/2 @ 312 CONDUCTOR ANHYDRITE T- B- 2234 ELEVATION TD 4645 FORMATION RAN PIPE @ DV TOOL ALT II DONE SX Y N Arbuckle Plug @ Ft. W/ SX Plug./Council @ Ft. W/ SX Anhydrite Base @ 2240 Ft. W/ 50 SX 1/2 Base Anhy. @ 1450 Ft. W/ 80 SX 1/2, 1/2 Plug @ 725 Ft. W/ 40 SX Bottom Surface @ 340 Ft. W/ 50 SX 40' Plug @ 40 Ft. W/ 10 SX RAT HOLE CIRC/W 15 SX MOUSE HOLE W/ 15 SX WATER WELL SX (Irr. Well Fond) TECHNICIAN SM DATE 11-1-96 Hauling TYPE OF CEMENT 60/40 67 1/4 Fl/6 Seal STARTING TIME : (AM/PM) DATE COMPLETION TIME 3 : (AM/PM) DATE 11-2-96 CEMENT COMPANY Allied