

API NUMBER 15-101-21,420-0000

LEASE NAME Steel "I"

WELL NUMBER 1

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

2280' Ft. from S Section Line

4950' Ft. from E Section Line

SEC. 21 TWP. 18S RGE. 30 (E) or (W)

COUNTY Iane

LEASE OPERATOR Donald C. Slawson

ADDRESS 104 S. Broadway Wichita, KS 67202

PHONE# (316) 263-3201 OPERATORS LICENSE NO. 5181

Character of Well D&A

Date Well Completed 10-1-87

Plugging Commenced 10-1-87

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 10-1-87

The plugging proposal was approved on _____ (date)

by _____ (KCC District Agent's Name).

Is AC0-1 filed? Yes If not, is well log attached? _____

Producing Formation _____ Depth to Top _____ Bottom _____ T.D. _____

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
		Surface	278'	8-5/8"		

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from ___ feet to ___ feet each set.

1st plug @ 2250' w/50 sx. 2nd plug @ 1470' w/ 80 sx. 3rd plug @ 300' w/40 sx. 4th plug @ 40' w/ 10 sx. 15 sx in rathole.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Allied Cementing Company License No. _____

Address P.O. Box 31 Russell, KS 67665

STATE OF Kansas COUNTY OF Sedgwick, ss.

William R. Horigan (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.


(Signature) WR Horigan

(Address) 104 S. Broadway Wichita, KS 67202

SUBSCRIBED AND SWORN TO before me this 27th day of Oct, 19 87

Elizabeth Cochran
 Notary Public

My Commission Expires:



OCT 29 1987
 10-29-87

NOTICE OF INTENTION TO DRILL

(see rules on reverse side)

Expected Spud Date... September 21 1987

API Number 15-101-21,420-0009

OPERATOR: License # 5181
Name SLAWSON, DONALD C.
Address 200 Douglas Building
City/State/Zip Wichita, Kansas 67202
Contact Person Bill Horigan
Phone (316) 263-3201

NW NW SW Sec. 21 Twp. 18 S. Rg. 30 East
2320' Ft. from South Line of Section
4950' Ft. from East Line of Section

(Note: Locate well on Section Plat on reverse side)

CONTRACTOR: License # 5657
Name Slawson Drig. Co.
City/State Great Bend, Kansas

Nearest lease or unit boundary line 330' feet
County Lane
Lease Name STEELE, I Well # 1
Ground surface elevation 2887' GR. (Seis) feet MSL

Well Drilled For: Well Class: Type Equipment:
X Oil Storage Infield X Mud Rotary
Gas Inj Pool Ext Air Rotary
OWWO Expl X Wildcat Cable

Domestic well within 330 feet: yes no
Municipal well within one mile: yes no
Depth to bottom of fresh water 140'
Depth to bottom of usable water 1100' 1930

If OWWO: old well info as follows:

Surface pipe by Alternate: 1 2 X
Surface pipe planned to be set 280'
Conductor pipe required
Projected Total Depth 4650' feet
Formation Mississippian

Operator
Well Name
Comp Date Old Total Depth

I certify that well will comply with K.S.A. 55-101, et seq., plus eventually plugging hole to KCC specifications. Western Kansas
Date 9/16/87 Signature of Operator or Agent Robert E. Jenkins Title District Geologist

For KCC Use:

Conductor Pipe Required feet; Minimum Surface Pipe Required 200 feet per Alt. X 2
This Authorization Expires 3-16-88 Effective 9-21-87 Approved By 9-16-87

Spud 9-21-87
Set 280 +

NW NW SW Sec. 21 Twp. 18 S. Rg. 30 East
X West

PLUGGING PROPOSAL IF ABOVE IS D & A

This plugging proposal will be reviewed and approved or revised at the time the district office is called prior to setting surface casing (call 7 a.m. to 5 p.m. workdays).

1st plug @ ft. deep 2170' or formation with 35BX feet of 60/40 Poz. w/6% Gel
2nd plug @ ft. deep 1150' or formation with 75BX feet of 60/40 Poz. w/6% Gel
3rd plug @ ft. deep 300' or formation with 40BX feet of 60/40 Poz. w/6% Gel
4th plug @ ft. deep 40' or formation with 10BX feet of 60/40 Poz. w/6% Gel
5th plug @ ft. deep or formation with feet of
(2) Rathole to surface minus 5 feet 10BX (b) Mousehole to surface minus 5 feet

PUSHER Bob Rowe
TD 4620 FORMATION MISS -
SURFACE PIPE 8 7/8 @ 278
ANEHYDRITE 2225 ELEVATION 2887
STARTING TIME & DATE 9-30-87 6:00 AM
COMPLETION TIME & DATE 9-15-87 9:15 AM
1st PLUG @ 2250 FT. W/ 50 SX SX
2nd PLUG @ 1470 FT. W/ 80 SX SX
3rd PLUG @ 300 FT. W/ 40 SX
4th PLUG @ 40-0 FT. W/ 10 SX
RAT HOLE CIRCULATED W/ 15 SX
MOUSE HOLE CIRCULATED W/ SX
WATER WELL PLUGGED W/ Seal - SX
CEMENT COMPANY 6/4 Poz 670 yd
TECHNICIAN Steve Dawson

RECEIVED
STATE COMMISSION
OCT 2 1987
10-2-87
CONSERVATION DIVISION
Wichita, Kansas