

To: 1 070600
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

TECHNICIAN'S PLUGGING REPORT

Operator License # 5393
Operator: A.L. Abercrombie, Inc.
Name &
Address 801 Union Center
Wichita, KS 67202

API NUMBER 15-101-21,490-0000
C NW NE, SEC. 30, T 19 S, R 27 W/EX
4620 feet from S section line
1980 feet from E section line
Lease Name Horton Well # 1
County Lane 151.61
Well Total Depth 4665 feet
Conductor Pipe: Size feet
Surface Casing: Size 8 5/8 feet 234

Abandoned Oil Well Gas Well Input Well SHD Well D&A X

Other well as hereinafter indicated

Plugging Contractor Abercrombie Drilling, Inc. License Number 5422

Address 801 Union Center, Wichita, KS 67202

Company to plug at: Hour: 12:30 p.m. Day: 10 Month: 10 Year: 19 88

Plugging proposal received from W.F. Dreiling

(company name) Abercrombie Drilling, Inc. (phone) 316-262-1841

were: to fill hole with heavy mud and spot cement through drill pipe Elevation 2730'
Anhydrite 2045-74'

1st plug at 2070' with 50 sx cement, 2nd plug at 1150' with 80 sx cement,

3rd plug at 600' with 40 sx cement, 4th plug at 260' with 40 sx cement,

5th plug at 40' with 10 sx cement,

6th plug to circulate rathole with 15 sx cement.

Plugging Proposal Received by Dan Goodrow
(TECHNICIAN)

Plugging Operations attended by Agent?: All X Part None

Operations Completed: Hour: 2:30 p.m. Day: 10 Month: 10 Year: 19 88

ACTUAL PLUGGING REPORT 1st plug at 2070' with 50 sx cement,

2nd plug at 1150' with 80 sx cement,

3rd plug at 600' with 40 sx cement,

4th plug at 260' with 40 sx cement,

5th plug at 40' with 10 sx cement,

6th plug to circulate rathole with 15 sx cement.

Remarks: Used 60/40 Pozmix 6% gel by B.J. Titan.
(If additional description is necessary, use BACK of this form.)

INVOICED observe this plugging.

DATE 10-27-88

INV. NO. 22755

Signed Dan Goodrow
(TECHNICIAN)