

LEASE NAME Eaton A

WELL NUMBER 1/14

4950 Ft. from ^NX Section Line

1320 Ft. from ^WX Section Line

SEC. 14 TWP. 17S RGE. 29W (N or W)

COUNTY Lane

Date Well Completed 1987

Plugging Commenced 12/28/01

Plugging Completed 12/28/01

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Whitetail Crude, Inc

ADDRESS P O Box 544, Ness City, KS 67560-0544

PHONE (785) 798-3641 OPERATORS LICENSE NO. 31627

Character of Well oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 12/26/01 (date)

by Richard Lacy (KCC District Agent's Name).

Is ACO-1 filed? yes If not, is well log attached? _____

Producing Formation Marmaton-Cherokee Depth to Top _____ Bottom T.D. 4600

PBTS 4589

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				<u>4 1/2"</u>	<u>4599</u>	<u>-0-</u>

RECEIVED
FEB 28 4 2002
KCC WICHITA 2002

Describe in detail the manner in which the well was plugged, indicating where the mud fluid placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each.
Sanded off the bottom perfs & capped with 4 sks of cement thru a dump bailer. Plug is @ 3500,

Swift Services on location 12/28/01. Mixed 150 sks & 400# of hulls, pumped down 4 1/2" casing 400# maximum pressure. Checked backside & it held pressure. Cement fell 350', went back later & topped off the 4 1/2" to surface with 20 sks.


Name of Plugging Contractor Swift Service, Inc License No. _____

Address P O Box 466, Ness City, KS 67560

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Whitetail Crude, Inc

STATE OF Kansas COUNTY OF Ness, ss.

Mike J. Fritzler, President of Whitetail Crude, Inc (Employee of Operator) or (Operator) above-described well, being first duly sworn on oath, says: That I have knowledge of the facts stated, and matters herein contained and the log of the above-described well as filed to the same are true and correct, so help me God.



(Signature) Mike J. Fritzler
MIKE J. FRITZLER, President
(Address) P O Box 544, Ness City, KS 67560-0544

SUBSCRIBED AND SWORN TO before me this 14th day of January, 2002

Debra Kerr
Debra Kerr Notary Public

My Commission Expires: 4/20/05

USE ONLY ONE SIDE OF EACH FORM

OK

