

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 200 Colorado Derby Building
 Wichita, Kansas 67202

WELL PLUGGING RECORD
 K.A.R.-82-3-117

API NUMBER 15-101-21,493-0000

LEASE NAME Schriock

WELL NUMBER A-1

2310 Ft. from S Section Line

2970 Ft. from E Section Line

SEC. 14 TWP. 17 RGE. 29 (E) or (W)

COUNTY Lane

Date Well Completed 11-11-88

Plugging Commenced 11-11-88

Plugging Completed 11-11-88

RECEIVED
 STATE CORPORATION COMMISSION

DEC 6 1988
 12-06-1988
 CONSERVATION DIVISION

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

LEASE OPERATOR Conservation Development, Inc.

ADDRESS RR. 1 Box 18, Paradise, Kansas 67658

PHONE# (913) 998-4413 OPERATORS LICENSE NO. 6194

Character of Well D & A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on November 9, 1988 (date)

by N/A (KCC District Agent's Name).

Is ACO-1 filed? no If not, is well log attached? YES

Producing Formation — Depth to Top — Bottom — T.D. —

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
	Surface Pipe	0	211'	8 5/8	5 jts.	0

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from feet to feet each set 2220' 50sks, 1300' 80sks, 240' 40sks, 40' 10sks, Rat hole 15sks Total 195sks 60/40 poz 6% gel Plug down 7:30 P.M. 11-11-88

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Western Kansas Drilling, Inc. License No. 4083

Address 2700 Oak, P.O. Box 126, Hays, Kansas 67601

STATE OF Kansas COUNTY OF Russell, ss.

(Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above-described well as filed the the same are true and correct, so help me God.

(Signature) Lewis E. Erb

(Address) RR 1, Box 18 Paradise, Ks. 67658

SUBSCRIBED AND SWORN TO before me this 2nd day of December, 19 88

Vernita V. Scott
 Notary Public

My Commission Expires: 4/3/91



NOTICE OF INTENTION TO DRILL

(see rules on reverse side)

Expected Spud Date. 11 4 88 month day year

API Number 15-101-21,493-0000

OPERATOR: License # 6194 Name E.S.P. Development, Inc. Address RR 1 Box 18 City/State/Zip Paradise, Kansas 67658 Contact Person Lewis Eulert Phone 913-998-4413

NE NE SW Sec. 14 Twp. 17 S. Rg. 29 East West 2310 2970 Ft. from South Line of Section Ft. from East Line of Section

(Note: Locate well on Section Plat on reverse side)

Nearest lease or unit boundary line 2310 feet County Lane

CONTRACTOR: License # 4083 Name Western Kansas Drilling, Inc. City/State Hays, Kansas 67601

Lease Name Schriock Well # A-1

Ground surface elevation N/A feet MSL

Well Drilled For: X Oil Storage Infield Mud Rotary Gas Inj Pool Ext Air Rotary OWWO Expl Wildcat Cable

Domestic well within 330 feet: yes XX no

Municipal well within one mile: yes XX no

Depth to bottom of fresh water 180

Depth to bottom of usable water 1200

Surface pipe by Alternate: 1 2 X

Surface pipe planned to be set 200+

Conductor pipe required

Projected Total Depth 4600 feet

Formation Mississippian

If OWWO: old well info as follows:

Operator Well Name Comp Date Old Total Depth

I certify that well will comply with K.S.A. 55-101, et seq. plus eventually plugging-hole to KCC specifications.

Date 11-1-88 Signature of Operator or Agent Frank Taggart Title Agent

For KCC Use:

Conductor Pipe Required 5-2-89 feet; Minimum Surface Pipe Required 200 feet per Alt. X (2)

This Authorization Expires 5-2-89 Approved By LKM 11-2-88

SPUD 11-5-88

878-220

11-15-1988

RECEIVED STATE COMMISSION NOV 15 1988

PLUGGING PROPOSAL IF ABOVE IS D & A

This plugging proposal will be reviewed and approved or revised at the time the district office is called prior to setting surface casing (call 7 a.m. to 5 p.m. workdays)

1st plug @ ft. deep Base of Anhy or formation with 50sks feet of 60/40 poz. 6% gel
2nd plug @ ft. deep Dakota or formation with 80sks feet of
3rd plug @ ft. deep Base Surface Pipe or formation with 40sks feet of
4th plug @ ft. deep 40' or formation with 10sks feet of
5th plug @ ft. deep Rat Hole or formation with 15sks feet of

(2) Rathole to surface minus 5 feet Mouse Hole 10sks (b) Mousehole to surface minus 5 feet

PUSHER Greg Michalitsen TD 4620' FORMATION MISS SURFACE PIPE 8 7/8 @ 2 1/1 ANHYDRITE 2196-2225 ELEVATION 2797 K B STARTING TIME & DATE 5:15 P.M. 11-1-88 COMPLETION TIME & DATE 7:30 P.M. 11-1-88 1st PLUG @ 2220 FT. W/ 50 SX 2nd PLUG @ 1300 FT. W/ 80 SX 3rd PLUG @ 240 FT. W/ 40 SX 4th PLUG @ 40 FT. W/ 10 SX RAT HOLE CIRCULATED W/ 15 SX MOUSE HOLE CIRCULATED W/ 1000 SX WATER WELL PLUGGED W/ 1000 SX CEMENT COMPANY Allied. TECHNICIAN R.L. 60/40 60/60 gel