

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15-101-21,366-0000

LEASE NAME Riley

WELL NUMBER 1

SPOT LOCATION SW/4 NW/4 SE/4

SEC. 15 TWP. 17S RGE. 29W (E/for(W))

COUNTY Lane

Date Well Completed 3/12/87

Plugging Commenced 3/12/87

Plugging Completed 3/12/87

TYPE OR PRINT

NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE OPERATOR ESP Development, Inc.

ADDRESS R. R. #1, Box 13, Paradise, Kansas 67658

PHONE # 913, 998-4413 OPERATORS LICENSE NO. 6194

Character of Well D & A  
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Dodge City, Ks. 676801 - Dan Goodrow

Is ACO-1 filed? yes If not, is well log attached? \_\_\_\_\_

Producing formation D/A Depth to top \_\_\_\_\_ bottom \_\_\_\_\_ T.D. 4,615'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8 5/8"	361'	-0-

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set.

1st Plug @ 2220' w/50 sx cement; 2nd Plug @ 1475' w/80 sx cement;

3rd Plug @ 400' w/40 sx cement; 4th plug @ 40' w/10 sx cement;

15 sx cement in rathole

195 sx 60/40 Pozmix, 6% Gel

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Red Tiger Drilling Company License No. 5302

Address 1720 KSB Building, Wichita, Kansas 67202

STATE OF \_\_\_\_\_ COUNTY OF \_\_\_\_\_, ss.

LEWIS EHLERT (employee of operator) or  
(operator) of above-described well, being first duly sworn on oath, says: That  
I have knowledge of the facts, statements, and matters herein contained and  
the log of the above-described well as filed that the same are true and  
correct, so help me God.

(Signature) Lewis Ehler

(Address) RR 1 Box 18 Paradise, Ks 67658

SUBSCRIBED AND SWORN TO before me this 1st day of April, 1987

My Commission expires: 4/3/87



04-02-1987  
APR 2 1987

Form CP-4  
Revised 01-84

NOTICE OF INTENTION TO DRILL

(see rules on reverse side)

Starting Date 2 18 86 month day year

OPERATOR: License # 6194 Name ESP DEVELOPMENT, INC. Address RR #1, Box 18 City/State/Zip Paradise, Kansas 67658 Contact Person Bud Eulert Phone 913-998-4413

CONTRACTOR: License # 5302 Name Red Tiger Drilling Co. City/State Wichita, Kansas 67202 Well Drilled For 1720 KS State Bond Well Class: Type Equipment: X Oil SWD Infield X Mud Rotary Gas Inj X Pool Ext Air Rotary OWWO Expl Wildcat Cable

IF OWWO: old well info as follows: Operator Well Name Comp Date Old Total Depth

I certify that well will comply with K.S.A. 55-101, et seq., plus eventually plugging hole to specifications. Date 2-13-87 Signature of Operator or Agent

For KCC Use: Conductor Pipe Required feet; Minimum Surface Pipe Required feet per Alt. This Authorization Expires 8-13-87

API Number 15-101-21,366-0000 1770 FSL; 2110 FEL SE 1/4 Sec. 15 Twp. 17 S, Rg. 29W East X West 1770 2110 Ft. from South Line of Section Ft. from East Line of Section

(Note: Locate well on Section Plat on reverse side) Nearest lease or unit boundary line 530 feet County Lane Lease Name Riley Well # 1 Ground surface elevation feet MSL Domestic well within 330 feet: yes X no Municipal well within one mile: yes X no Depth to bottom of fresh water 250-200 Depth to bottom of usable water 1425 Surface pipe by Alternate: 1 X Surface pipe planned to be set 350 Conductor pipe required N.A Projected Total Depth 4550 feet Formation Mississippian

Handwritten signature: Mike Waggner

BY RED TIGER DRILLING CO.

1770 FSL; 2110 FEL SE 1/4 15 17 29W East West

More in 3-2-87 set 8 7/8 @ 350' per Waggner

PLUGGING PROPOSAL IF ABOVE IS D & A

This plugging proposal will be reviewed and approved or revised at the time the district office is called prior to setting surface casing (call 7 a.m. to 5 p.m. workdays).

1st plug @ 2260 feet depth with 50 60-40 poz., 6% gel
2nd plug @ 1460 feet depth with 100
3rd plug @ 410 feet depth with 50
4th plug @ 40 feet depth with
5th plug @ feet depth with
(2) Rathole with (b) Mousehole with

Handwritten log:
PUSHER Mike Waggner
TD 4615 FORMATION MISS
SURFACE PIPE 8 7/8" @ 368'
ANHYDRITE 2187' ELEVATION 2799'
STARTING TIME & DATE 2:00 PM
COMPLETION TIME & DATE 3:45 3-12-87
1st PLUG @ 2220 FT. W/ 50 SX
2nd PLUG @ 1475 FT. W/ 80 SX
3rd PLUG @ 400 FT. W/ 40 SX
4th PLUG @ 40 FT. W/ 10 SX
RAT HOLE CIRCULATED W/ 15 SX
MOUSE HOLE CIRCULATED W/ SX
WATER WELL PLUGGED W/ 10' and over SX
CEMENT COMPANY ALLIED -
TECHNICIAN D.G.
6940 poz. 670 gel
Waggner all by D.G.
03-18-1987
STATE OF KANSAS COMMISSION
DIVISION OF MINES AND GEOLOGY
WICHITA, KANSAS