


STATE OF KANSAS  
STATE CORPORATION COMMISSION

15761 20185 0000

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to  
Conservation Division  
State Corporation Comm.  
245 North Water  
Wichita, KS 67202

Lane \_\_\_\_\_ County \_\_\_\_\_ Sec. 12 Twp. 17 Rge. 29 E/W  
Location as "NE/CNW $\frac{1}{2}$ SW $\frac{1}{2}$ " or footage from lines \_\_\_\_\_  
Eaton #1 C SW NE  
Lease Owner Tomlinson Oil Co., Inc.  
Lease Name Eaton #1 Well No. \_\_\_\_\_  
Office Address Great Bend, Kansas 67530  
Character of Well (Completed as Oil, Gas or Dry Hole) \_\_\_\_\_



Locate well correctly on above  
Section Plat

Date Well completed \_\_\_\_\_ 19\_\_\_\_  
Application for plugging filed \_\_\_\_\_ 19\_\_\_\_  
Application for plugging approved \_\_\_\_\_ 19\_\_\_\_  
Plugging commenced 4/7/77 \_\_\_\_\_ 19\_\_\_\_  
Plugging completed 4/11/77 \_\_\_\_\_ 19\_\_\_\_  
Reason for abandonment of well or producing formation  
depleted. \_\_\_\_\_

If a producing well is abandoned, date of last production \_\_\_\_\_ 19\_\_\_\_

Was permission obtained from the Conservation Division or  
its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Balthazor  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 4625  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8	329	none
				5 1/2"	4617	3036

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Set wood plug at 4200' and sanded to ~~47~~ 4170', ran 4 sacks cement. Shot pipe at ~~390~~ 3505', 3217', 3025', pulled 93 joints. Allied plugged well with 3 sacks hulls, 70 sacks cement, 3 sacks gel, plug and 60 sacks cement.

PLUGGING COMPLETE.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor KELSO CASING PULLING  
CHASE, KANSAS

STATE OF KANSAS COUNTY OF RICE, ss.  
R. DARRELL KELSO (employee of owner) or (owner or operator)  
of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) R. Darrell Kelso  
CHASE, KANSAS  
(Address)

SUBSCRIBED AND SWORN TO before me this 15th day of April, 19 77

Margaret Melcher  
Notary Public.

My commission expires \_\_\_\_\_



04-19-1977

GABBERT-JONES, INC.  
 WICHITA, KANSAS  
 DRILLERS' WELL LOG

Eaton #1  
 C-SW-NE Sec 12-17S-29W  
 Lane County Kansas

Commenced: 7-6-76

Completed: 7-17-76

OPERATOR: TOMLINSON OIL CO.

15-101-20185-0000

Depth		Formation	Remarks
From	to		
0	110	Surface Clay-Sand:	Ran 9 jts of used 8 5/8" 28#
110	334	Sand-Shale	csg set @ 329' Cemented w/
334	1325	Shale	225 sks Common 2% Gel
1325	1555	Shale-Sand	3% CC PD @ 7:10 p.m.
1555	1720	Shale	7-6-76 Cement Circ
1720	1940	Sand	
1940	2185	Shale-Redbed	
2185	2215	Anhy	
2215	2615	Shale	
2615	4050	Lime-Shale	
4050	4625	Lime	
	4625 - TD		Ran 146 jts of 14 1/2" 5 1/2" csg set @ 4617' Cemented w/175 sks salt sat Posmix PD @ 11:45 a.m. 7-17-76

STATE OF KANSAS )  
 ) SS  
 COUNTY OF SEDGWICK)

I, the undersigned, being duly sworn on oath, state that the above Drillers Log is true and correct to the best of my knowledge and belief and according to the records of this office.


GABBERT-JONES, INC.

*James S. Sutton II*  
 JAMES S. SUTTON II

Subscribed and sworn to before me this 21st day of July, 1976.

*Elizabeth J. Edwards*  
 ELIZABETH J. EDWARDS

My Commission expires February 6, 1979.



08-22-1977