

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE NAME Eaton

WELL NUMBER #1

 Ft. from S Section Line

 Ft. from E Section Line

SEC. 12 TWP. 17S RGE. 29W (S) or (W)

COUNTY Lane

Date Well Completed

Plugging Commenced 12/3/98

Plugging Completed 12/3/98

EASE OPERATOR Whitetail Crude, Inc

ADDRESS P O Box 544, Ness City, KS 67560-0544

PHONE () 785-798-3641 OPERATORS LICENSE NO. 31627

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on (date)

by Kevin Strube (KCC District Agent's Name).

Is ACO-1 filed? If not, is well log attached?

Producing Formation Kansas City/Lansing Depth to Top 4204 Bottom 4553 T.D. 4563

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
Kansas City		0	343	8 5/8	343	-0-
Lansing		0	4563	5 1/2	4563	644' pulled out

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug are used, state the character of same and depth placed, from feet to feet each set. Sanded the bottom perfs off & spotted 4 sks of cement with a dump bailer. Perforated 5 1/2 @ 1200' & mixed 60 sks of 60/40 6% gel with 50# of hulls & displaced to 900'. Shot the pipe off @ 644' pulled 1 joint & mixed a 40 sk plug & displaced to 600'. Pulled pipe to 360' & pumped a 40 sk plug, pulled the pipe out and topped off with 10 sks

Name of Plugging Contractor Allied Cementing Co Inc License No.

Address P O Box 31, Russell, KS 67665 12-14-1998


NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Whitetail Crude, Inc

STATE OF Kansas COUNTY OF Ness, ss.

Mike J. Fritzler, President of Whitetail Crude, Inc (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts and statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Mike J. Fritzler

(Address) P O Box 544, Ness City, KS 67560-0544



SUBSCRIBED AND SWORN TO before me this 10th day of December, 19 98

Debra Kerr
Notary Public Debra Kerr

My Commission Expires: 4/20/98

USE ONLY ONE SIDE OF EACH FORM