

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Bldg.
Wichita, Kansas 67202

15101-20613-0000
RECEIVED Form CP-4
STATE CORPORATION COMMISSION Rev. 12-15-80

AUG 02 1982
8-2-82
CONSERVATION DIVISION
Wichita, Kansas

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit

COUNTY Lane SEC. 13 TWP. 17S RGE. 29W E/W
Location as in quarters or footage from lines:
C of NW SE

Locate Well
correctly on above
Section Platt.

Lease Owner Donald C. Slawson
Lease Name Sutton J-1 Well No. _____
Office Address 200 Douglas Bldg. Wichita, Kansas 67202
Character of Well (Completed as Oil, Gas or Dry Hole): _____
Date Well Completed _____
Application for plugging filed _____
Plugging commenced 7-26-82
Plugging completed 7-29-82
Reason for abandonment of well or producing formation _____
Depleted
Was permission obtained from the Conservation Division or it's
Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Steve Durrant
Producing formation _____ Depth to top _____ bottom T.D. 4570'
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
				8-5/8"	373'	none
				4-1/2"	4569'	3032'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.


Plugged off bottom with sand to 4100' and ran 4 sacks cement. Shot casing @3570', 3405', 3210' and 3025'. Pulled a total of 74 joints of 4-1/2" casing. Squeezed hole with 3 sacks hulls, 15 sacks gel, 70 sacks cement, 1 sack hulls, 15 sacks gel, released plug and displaced with 80 sacks cement.
Plugging Complete.

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Kelso Casing Pulling

STATE OF Kansas COUNTY OF Rice, ss.
R. Darrell Kelso (employee of owner) or (owner or operator) of the
above-described well, being first duly sworn on oath, says: That I have knowledge of the
facts, statements, and matters herein contained and the log of the above-described well as
filed and that the same are true and correct. So help me God.

(Signature) R. Darrell Kelso
Box 347 Chase, Ks. 67524
(Address)

SUBSCRIBED AND SWORN TO before me this 30th day of July, 19 82

My Commission expires:  IRENE HOOVER
State of Kansas
My Comm. Exp. Aug. 15, 1985

Irene Hoover
Notary Public.

Sun Oilwell Cementing
A Division of BJ Hughes, Inc.

P.O. Box 169
GREAT BEND, KS. 67530

Cementing Ticket
and Invoice Number

No 11546

Date	Customer Order No.	Sect.	Twp.	Range	Truck Called Out	On Location	Job Began	Job Completed
7-29-82		13	17S	29W	7:00 AM	4:00 AM	10:00 AM	10:45 AM

Owner	Contractor	Charge To
Donald C. Slawson	Kelso	Donald C. Slawson

Mailing Address	City	State

Well No. & Form	Place	County	State
Sutton J#1	4+23-2S 1/4 W-2S	Lane	Kansas

Depth of Well	Depth of Job	Casing	New	Used	Size	Weight	Size of Hole	Amt. and Kind of Cement	Cement Left in casing by	Request Necessity	feet
4550	1						150 5/8				

Kind of Job	Drillpipe	Tubing	Rotary	Cable	Truck No.
PTA (New Well)					#24

Condition of Well at time of Cementing	Type of Plugs
Normal	Wooden dry hole

Pressure Circulating	Minimum	Maximum
0		700

Time Required Mixing Cement	min. Making Change	min. Pumping Cement

Remarks: Mixed 150 sks 50/50 poz-mix 4% Bel 3% ACL

Price Reference No. _____

Price of Job 650.00

Second Stage 90.00

Standby Truck 743.00

Other Charges _____

Total Charges 743.00

mixed 3 sks hulls followed by 15 sks gel followed by 70 sks 50/50 followed by 19K hulls followed by 15 sks gel followed by releasing plug followed by 30 sks 50/50

Thanks! Borden Plugdown at 10:45 AM

Cement	Material Left on Location
Borden Fitz	

Helper	District	State
Mike D. Verde	Oakley	Kansas

The above job was done under supervision of the owner, operator, or his agent whose signature appears below.

Agent of contractor or operator

Sales Ticket for Materials Only

Quantity Sacks	BRAND AND TYPE	PRICE	Total
75	Common	6.00	450.00
75	Poz-mix	2.50	187.50
4	Hulls		56.00
Cc Cl.	378 lbs	.21 ¹⁰	79.38
AM.CI			
Gel	3504 lbs	6.10 ^{net}	213.74
Plugs	1 Wooden dry hole	9.00	9.00
	Handling & Dumping	.42	138.00
	Delivered by Truck No. T-27	.68	342.72
	Delivered from Oakley	.03	13.77
	Signature of operator	Total	2230.11

RECEIVED
STATE CORPORATION COMMISSION

AUG 02 1982

CONSERVATION DIVISION
Wichita, Kansas