

API NUMBER 15-101-20838-0000

LEASE NAME Hazel Eaton

WELL NUMBER 1-13

4950 Ft. from (S) Section Line

990 Ft. from (E) Section Line

SEC. 13 TWP. 17 RGE. 29 (E) or (W)

COUNTY Lane

Date Well Completed 10/3/83

Plugging Commenced 6/16/95

Plugging Completed 6/16/95

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR PPSI - Petroleum Property Services, Inc.

ADDRESS 155 N. Market #1010 Wichita, KS. 67202

PHONE#(316) 265-3351 OPERATORS LICENSE NO. 31142

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 6/14/95 (date)

by Steve Middleton (KCC District Agent's Name).

Is ACO-1 filed? Yes if not, is well log attached? _____

Producing Formation Marmaton & Cherokee Depth to Top 4318 Bottom 4566 T.D. 4619

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
Marmaton	Oil & Water	4467	86	8 3/8	331	None
Cherokee	Oil & Water	4501	37	4 1/2	4617	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from feet to feet each set

Pressure test 8 5/8 - 4 1/2 Annulus to 500# held. Pump down 4 1/2 400# hulls 250 sx 60/40
Poz 8% GEI Max Press 700# Final pressure 300# with cement to surface.

Name of Plugging Contractor Petroelum Property Services, Inc. License No. _____

Address 155 N. Market #1010 Wichita, KS 67202

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Petroleum Property Services, Inc.

STATE OF Kansas COUNTY OF Sedgwick, ss.


Jim Thatcher

(Employee of Operator) or (Operator) o

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above-described well as filed the the same are true and correct, so help me God.

(Signature) Jim Thatcher

(Address) 155 N. Market #1010 Wichita, KS. 67202



AND SWORN TO before me this 5th day of July, 19 95

Elizabeth S. Garrison
Notary Public

My Commission Expires: September 12, 1998

USE ONLY ONE SIDE OF EACH FORM

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
200 Colorado Derby Building
Wichita, Kansas 67202

FORM CP-1
Rev. 03/92

WELL PLUGGING APPLICATION FORM
(PLEASE TYPE FORM and File ONE Copy)

API # 15-101-20838 (Identifier number of this well). This must be listed for wells drilled since 1967; if no API# was issued, indicate spud or completion date.

WELL OPERATOR Petroleum Property Services, Inc. KCC LICENSE # 31142
(owner/company name) (operator's)

ADDRESS 155 N. Market #1010 CITY Wichita

STATE Kansas ZIP CODE 67202 CONTACT PHONE # (316) 265-3351

LEASE Hazel Eaton WELL# 1-13 SEC. 13 T. 17 R. 29 (East/West)

- NW - NE - NE SPOT LOCATION/QQQQ COUNTY Lane

4950 FEET (in exact footage) FROM (S)N (circle one) LINE OF SECTION (NOT Lease Line)

990 FEET (in exact footage) FROM (E)W (circle one) LINE OF SECTION (NOT Lease Line)

Check One: OIL WELL GAS WELL D&A SWD/ENHR WELL DOCKET# _____

CONDUCTOR CASING SIZE _____ SET AT _____ CEMENTED WITH _____ SACKS

SURFACE CASING SIZE 8 5/8 SET AT 331 CEMENTED WITH 190 SACKS

PRODUCTION CASING SIZE 4 1/2 SET AT 4617 CEMENTED WITH 175 SACKS

LIST (ALL) PERFORATIONS and BRIDGEPLUG SETS: 4465-68, 4480-86, 4501-04, 4506-09, 4529-31,

ELEVATION GR 2780 Perf at 1350' and cement to surface with 250 sx 4535-37
KB 2785 T.D. 4619 PBD 4585 ANHYDRITE DEPTH 2166
(G.L./K.B.) (Stone Corral Formation)

CONDITION OF WELL: GOOD POOR CASING LEAK JUNK IN HOLE

PROPOSED METHOD OF PLUGGING Per KCC Recommendation

(If additional space is needed attach separate page)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? Yes IS ACO-1 FILED? Yes

If not explain why? _____

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et. seq. AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

LIST NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

Bill Hammack PHONE# (913) 483-1558

ADDRESS P.O. Box 551 City/State Russell, KS.

PLUGGING CONTRACTOR Petroleum Property Services, Inc. KCC LICENSE # 31142
(company name) (contractor's)

ADDRESS 155 N. Market #1010 Wichita, KS. 67202 PHONE # (316) 265-3351

PROPOSED DATE AND HOUR OF PLUGGING (If Known?) _____

PAYMENT OF THE PLUGGING FEE (K.A.R. 82-3-118) WILL BE GUARANTEED BY OPERATOR OR AGENT

DATE: _____ AUTHORIZED OPERATOR/AGENT: [Signature]
(signature)

Petro-Log

API# 15-101-20838-0000

Radiation Guard Log

MARKED

COMPANY GEAR PETROLEUM COMPANY INC.

WELL HAZEL EATON #1-13

FIELD _____

COUNTY LANE STATE KANSAS

Location NW - NE - NE
 Sec. 13 Twp. 17S Rge. 29W

Other Services:

Permanent Datum: GROUND LEVEL Elev. 2780
 Log Measured From K.B., 5 Ft. Above Perm. Datum
 Drilling Measured From KELLY BUSHING

Elev.: K.B. 2785
 D.F. _____
 G.L. 2780

Date	10/2/83				
Run No.	ONE				
Depth—Driller	4619				
Depth—Logger	4619				
Btm. Log Inter.	4618				
Top Log Inter.	SURF				
Casing—Driller	8 5/8 @ 330	@	@	@	@
Casing—Logger					
Bit Size	7 7/8				
Type Fluid in Hole	SALT CLAY STARCH				
Dens.	9.5	53			
Visc.					
pH	9.0	9.6 ml	ml	ml	ml
Fluid Loss					
Source of Sample	FLOWLINE				
R ₁ @ Meas. Temp.	.4 @ 75 °F	@ °F	@ °F	@ °F	@ °F
R ₂ @ Meas. Temp.	.3 @ 75 °F	@ °F	@ °F	@ °F	@ °F
R ₃ @ Meas. Temp.	.6 @ 75 °F	@ °F	@ °F	@ °F	@ °F
Source: R ₁ R ₂ R ₃	CHARTS				
R ₁ @ BHT	.2 @ 121 °F	@ °F	@ °F	@ °F	@ °F
Time Since Circ.	2 HOURS				
Max. Rec. Temp.	121 °F	SURF °F	°F	°F	°F
Equip. Location	87058 OAKLEY				
Recorded By	J. PORTER				
Witnessed By	MR. BRYCE BILEMAN				