

Lease Name & WELL NUMBER Hazel Eaton #2-13

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

4920 Ft. from S Section Line

330 Ft. from E Section Line

LEASE OPERATOR Petroleum Property Services, Inc.

SEC. 13 TWP. 17 RGE. 29 (S) or (W)

ADDRESS 155 N. Market #1010 Wichita, KS. 67202

COUNTY Lane

PHONE/(316) 265-3351 OPERATORS LICENSE NO. 31142

Date Well Completed 1/8/84

Character of Well Oil

Plugging Commenced 6/16/95

(Oil, Gas, O&A, SWD, Input, Water Supply Well)

Plugging Completed 6/16/95

The plugging proposal was approved on 6/14/95 (date)

by Steve Middleton (KCC District Agent's Name).

Is ACO-1 filed? Yes If not, is well log attached? _____

Producing Formation Marmaton/Pawnee Depth to Top 4321 Bottom 4582 T.D. 4620

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
Marmaton	Oil & Water	4379	4410	8 5/8	333	None
Pawnee	Oil & Water	4421	27	4 1/2	4598	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from ___ feet to ___ feet each section.

Pressure 8 5/8 - 4 1/2 annulus to 300%. Held. Pump down 4 1/2 400# bulls with 250 ex 60/40 Poz. 8% Gel. Max press 500#. final press 200# with cement to surface

Name of Plugging Contractor Petroleum Property Services, Inc. License No. _____

Address 155 N. Market #1010 Wichita, Ks. 67202

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Petroleum Property Services, Inc.

STATE OF Kansas COUNTY OF Sedgwick, ss.

Jim Thatcher (Employee of Operator) or (Operator) c above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above-described well as filed the the same are true and correct, so help me God.

(Signature) Jim Thatcher

(Address) 155 N. Market #1010 Wichita, KS 67202

SUBSCRIBED AND SWORN TO before me this 5th day of July, 19 95

ELIZABETH S. GARRISON
NOTARY PUBLIC
STATE OF KANSAS
My Appt. Exp. 7/21/98

Elizabeth S. Garrison
Notary Public

My Commission Expires: September 12, 1998

USE ONLY ONE SIDE OF EACH FORM

Kent C. 13-17s-29W

~~15T~~

Petro-Log

Radiation Guard Log
API #15-101-20889-0000

COMPANY GEAR PETROLEUM COMPANY, INC.

WELL EATON #2-13

FIELD _____

COUNTY LANE STATE KANSAS

Location SE-NE-NE Other Services: _____

Sec. 13 Twp. 17S Rge. 29W

Permanent Datum: GROUND LEVEL Elev. 2779 Elev.: K.B. 2786

Log Measured From K.B., 7 Ft. Above Perm. Datum D.F.

Drilling Measured From KELLY BUSHING G.L. 2779

Date	1-7-84				
Run No.	ONE				
Depth—Driller	4620				
Depth—Logger	4624				
Btm. Log Inter.	4623				
Top Log Inter.	SURF.				
Casing—Driller	8 5/8 @ 338	•	•	•	•
Casing—Logger					
Bit Size	7 7/8				
Type Fluid in Hole	CHEMICAL MUD				
Dens. Visc.	9.2 67				
pH Fluid Loss	10.0 10.4ml		ml	ml	ml
Source of Sample	FLOWLINE				
R ₁₀ @ Meas. Temp.	.77 @ 78 °F	•	•	•	•
R ₅ @ Meas. Temp.	.58 @ 78 °F	•	•	•	•
R ₁ @ Meas. Temp.	1.15 @ 78 °F	•	•	•	•
Source: R ₁₀ R ₅ R ₁	CHARTS				
R ₁₀ @ BHT	.49 @ 122 °F	•	•	•	•
Time Since Circ.	2 HRS.				
Max. Rec. Temp.	122 °F		°F	°F	°F
Equip. Location	84166 G.B.				
Recorded By	DAN THOMPSON				
Witnessed By	MR. CASEY GALLOWAY				

STATE

JAN 10 1985

CONSULTING
WICHITA, KANSAS