


15-101-20069-0000

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
P. O. Box 17027  
Wichita, Kansas 67217  
NORTH



Locate well correctly on above Section Plat

Lane \_\_\_\_\_ County. Sec. 4 Twp. 18S Rge. 29W (E) \_\_\_\_\_ (W) X  
Location as "NE/CNWxSWx" or footage from lines NW SW NE  
Lease Owner Thunderbird Drilling, Inc.  
Lease Name Pinkston "A" Well No. 1  
Office Address Suite 780, 7701 E. Kellogg, Wichita, Kansas 67218  
Character of Well (completed as Oil, Gas or Dry Hole) D & A  
Date well completed November 17 1973  
Application for plugging filed November 17 1973  
Application for plugging approved November 17 1973  
Plugging commenced November 17 1973  
Plugging completed November 17 1973  
Reason for abandonment of well or producing formation D & A

If a producing well is abandoned, date of last production \_\_\_\_\_ 19\_\_\_\_  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Mr. W.L. Nichols  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 4600 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	453'	-0-

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Filled hole w/mud & plugged @ 600' w/90 sx.  
50-50 pozmix, 6% Gel. Filled hole to 40'  
w/mud and set plug w/1/2 sk. hulls & 10 sx. cmt.

RECEIVED  
STATE CORPORATION COMMISSION  
NOV 28 1973  
11-28-73  
CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor Red Tiger Drilling Company  
Address 1720 Wichita Plaza, Wichita, Kansas 67202

STATE OF Kansas, COUNTY OF Sedgwick, ss.  
Linda H. Dickens (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Linda H. Dickens  
1720 Wichita Plaza, Wichita, Kansas 67202  
(Address)

SUBSCRIBED AND SWORN TO before me this 26th day of November, 1973

My commission expires May 24, 1977  
Linda C. Mauley Notary Public.



15-101-20069-0000

DRILLERS LOG

No. 1 Pinkston "A"

<b>CASING RECORD:</b>	<b>COMPANY:</b> Thunderbird Drilling, Inc.	<b>DESCRIPTION:</b>
8-5/8" @ 453'	<b>CONTRACTOR:</b> Red Tiger Drilling Co.	NW SW NE
w/250 sx cement	<b>COMMENCED:</b> November 2, 1973	4-185-29W
	<b>COMPLETED:</b> November 17, 1973	Lane County,
		Kansas
<b>TOTAL DEPTH:</b> 4,600'		

ELEVATION: 2753 Gr.

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>
Surface Hole	0	200
Shale	200	585
Shale & Redbed	585	1090
Shale	1090	1318
Blaine	1318	1337
Shale & Shells	1337	1560
Blaine Anhydrite	1560	1596
Shale	1596	1680
Sand	1680	1910
Shale	1910	2030
Shale & Lime & Anhydrite	2030	2180
Anhydrite Stringers & Shale	2180	2259
Shale & Lime	2259	2875
Lime	2875	4537
Lime & Chert	4537	4600

REMARKS

RECEIVED  
STATE CORPORATION COMMISSION  
NOV 28 1973  
11-28-73  
CONSERVATION DIVISION  
Wichita, Kansas

Anhydrite 2118-2155

I certify that this is a true and correct copy of the above log to the best of my knowledge.

RED TIGER DRILLING COMPANY

Linda H. Dickens  
Linda H. Dickens

Subscribed and sworn to before me this 26th day of November, 1973.

Linda C. Mowrey  
Notary Public

My Commission Expires:

May 24, 1977

