

Form CP-4
Rev. 12-15-80

15.101.2 0736.0000

COUNTY Lane SEC. 2 TWP. 18S RGE. 29W E/W
Location as in quarters or footage from lines:
C SW NW

Lease Owner Petroleum, Inc.
Lease Name DUTOIT Well No. 1
Office Address 800 R.H. Garvey Bldg., 300 W. Douglas, Wichita, KS
Character of Well (Completed as Oil, Gas or Dry Hole): Dry
Date Well Completed December 12, 1982
Application for plugging filed December 12, 1982
Plugging commenced December 12, 1982
Plugging completed December 12, 1982
Reason for abandonment of well or producing formation No commercial quantity of oil or gas encountered.
Was permission obtained from the Conservation Division or it's Agent's before plugging was commenced? YES

OIL, GAS OR WATER RECORDS

[illegible]

Set 1st plug @ 1380' with 70 sx.

Set 2nd plug @ 240' with 40 sx.

~~Set 3rd plug @ 40' Sol. Bridge with 10 sx~~

~~10 sx. in Rathole. 50-50 posmix, 4% gel, 3% c.c.~~

~~Plug was down @ 9:15 a.m., 12/08/82~~

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Abercrombie Drilling, Inc.
801 Union Center, Wichita, KS 67202

STATE OF Kansas COUNTY OF Sedgwick, ss.

Jack L. Partridge, Vice President (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature)

801 Union Center, Wichita, KS 67202


(Address)

SUBSCRIBED AND SWORN TO before me this 21st day of December, 19 82

My Commission expires: 7-13-85

Elizabeth Genderry

DEC 30 1982
12-30-82
CONSERVATION DIVISION
Wichita, Kansas



DRILLER'S LOG

STATE OF KANSAS
JAN 25 1983
1-25-83
WICHITA DIVISION
WICHITA, KANSAS

PETROLEUM, INC.
Dutoit #1
SW NW
2-18S-29W
Lane Co., KS

15-101-20736-0000

Commenced: 11-27-82
Completed: 12-21-82

Surface Casing: 206' of 8-5/8" cmtd.
w/160 sacks Common, 2% gel, 3% CC.

FORMATION

DEPTH

Surface Clay & Sand	0 - 210
Shale & Sand & Shells	210 - 728
Sand & Shale	728 - 1450
Shale	1450 - 1917
Shale & Lime	1917 - 2139
Anhydrite	2139 - 2167
Shale & Lime	2167 - 2527
Lime & Shale	2527 - 2560
Shale & Lime	2560 - 3240
Lime	3240 - 3380
Lime & Shale	3380 - 3757
Lime	3757 - 4280
Lime & Shale	4280 - 4336
Lime	4336 - 4596
Rotary Total Depth	4596


I do hereby certify that the foregoing statements are true and correct to the best of my knowledge.

PETROLEUM, INC.

Terry Naylor

Terry Naylor

STATE OF KANSAS: ss:



Subscribed and sworn before me this 24th day of January, 1983.

My Commission expires 12-20-83.

Lynn Adams
Notary Public