

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 200 Colorado Building
 Wichita, Kansas 67202

WELL PLUGGING RECORD
 K.A.R.-82-3-117

API NUMBER 15-101-21,481-0000

LEASE NAME G.R. Dodge Trust

WELL NUMBER #1

1650 Ft. from S Section Line

2310 Ft. from E Section Line

SEC. 6 TWP. 17S RGE. 29 (X) or (W)

COUNTY Lane

Date Well Completed 9-11-88

Plugging Commenced 9-11-88

Plugging Completed 9-11-88

RECEIVED
 SEP 16 1988
 9-16-88
 CONSERVATION DIVISION
 WICHITA, KANSAS
 TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

LEASE OPERATOR R & C Oil Operating, Inc.

ADDRESS P.O. Box 86 Plainville, Ks. 67663

PHONE#(913) 434-7434 OPERATORS LICENSE NO. 8914

Character of Well D & A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Dodge City

Is ACO-1 filed? Yes If not, is well log attached? _____

Producing Formation _____ Depth to Top _____ Bottom _____ T.D. 4625

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
Surface		0	297	8 5/8	305	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from ___ feet to ___ feet each set.

Filled hole with drilling mud to 2260. Plugged as follows:
50 sacks @ 2260', 80 sacks @ 1330', 50 sacks @ 330', 10 sacks @ 40', 15 sacks in rathole,
10 sacks in mousehole. Total of 215 sacks 60/40 Posmix with 6% gel

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor R & C Drilling Co. Inc. License No. 9087

Address P.O. Box 296 Hays, Ks. 67601

STATE OF Kansas COUNTY OF Rooks, ss.

Charles R. Ramsay (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Charles R. Ramsay

(Address) P.O. Box 86 Plainville, Ks. 67663

SUBSCRIBED AND SWORN TO before me this 15th day of Sept, 19 88

Irene Fellhoefer
 Notary Public

My Commission Expires: Irene Fellhoefer
State Notary Public

Rooks County, Kansas
 My Commission Expires 4-4-91

NOTICE OF INTENTION TO DRILL

(see rules on reverse side)

Expected Spud Date. 8-29-88 month day year

API Number 15-101-21,481-0000

OPERATOR: License # 8914
Name H & C Oil Operating Inc.
Address P.O. Box 86
City/State/Zip Plainville, Ks. 67663
Contact Person Charles R. Ramsay
Phone 913-434-7434

SW. NW. SE. Sec. 6 Twp. 17 S. Rg. 29
1650 Ft. from South Line of Section
2310 Ft. from East Line of Section

CONTRACTOR: License # 9087
Name R & C Drilling Co. 913 625 4548
City/State Hays, Kansas 67601

(Note: Locate well on Section Plat on reverse side)
Nearest lease or unit boundary line 330 feet

Well Drilled For: Well Class: Type Equipment:
X Oil Storage Infield X Mud Rotary
Gas Inj X Pool Ext. Air Rotary
OWWO Expl Wildcat Cable

Lease Name G.R. Dodge Trust Well # 1
Ground surface elevation est. 2825 feet MSL

If OWWO: old well info as follows:
Operator
Well Name
Comp Date Old Total Depth

Domestic well within 330 feet: yes X no
Municipal well within one mile: yes X no
Depth to bottom of fresh water 175 190'
Depth to bottom of usable water 1350

I certify that well will comply with K.S.A. 55-101, et seq., plus
Date 8-4-88 Signature of Operator or Agent Charles R. Ramsay

Surface pipe by Alternate 1 2 X
Surface pipe planned to be set 280
Conductor pipe required none
Projected Total Depth 4625 feet
Formation Mississippi

For KCC Use:
Conductor Pipe Required feet; Minimum Surface Pipe Required 220' feet per Alt. X 2
This Authorization Expires 2-5-89

Approved By LKM 9-5-88

EFFECTIVE DATE: 8-10-88

Spud 9-2-88

RECEIVED STATE CORPORATION COMMISSION SEP 16 1988

PLUGGING PROPOSAL IF ABOVE IS D & A

This plugging proposal will be reviewed and approved or revised at the time the district office is called prior to setting surface casing (call 7 a.m. to 5 p.m. workdays).

Table with 3 columns: Plug depth (ft.), Sacks, and Formation. Includes rows for 1st through 5th plugs and Rathole to surface.

(2) Rathole to surface minus 5 feet (b) Mousehole to surface minus 5 feet

Log table with columns: Formation, Surface Pipe, Anhydrite, Starting Time & Date, Completion Time & Date, Plug depth, Rat Hole Circulated, Mouse Hole Circulated, Water Well Plugged, Cement Company, Technician.

Handwritten notes: 7:30 AM 9-11-88, Com 10 AM 9-11-88, Allied