

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

Lane _____ County. Sec. 5 Twp. 17S Rge. 29 W
Location as "NE/CNW 1/4 SW 1/4" or footage from lines _____

C SE SE
Lease Owner Tomlinson Oil Co., Inc.
Lease Name Munsell Well No. 1

Office Address Suite 1030, 200 W. Douglas, Wichita, Ks.
Character of Well (Completed as Oil, Gas or Dry Hole) _____
Dry Hole


Date Well completed July 3, 1976
Application for plugging filed July 2, 1976
Application for plugging approved July 2, 1976
Plugging commenced July 3, 1976
Plugging completed July 3, 1976

Reason for abandonment of well or producing formation _____
Dry Hole

If a producing well is abandoned, date of last production _____
19 _____

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Gilbert Barthzar
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4580'
Show depth and thickness of all water, oil and gas formations.



Locate well correctly on above Section Plat

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Surface Hole		0	336'	8 5/8"	8 fts.	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Plugged through drill pipe at 850' w/70 sacks cement.
Plugged through drill pipe at 325' w/20 sacks cement.
Plugged through drill pipe at 40' w/10 sacks cement.

RECEIVED
AUG 27 1976
08-27-1976
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)


Name of Plugging Contractor Gabbert-Jones, Inc.

STATE OF KANSAS COUNTY OF SEDGWICK, ss.

J. Corry Tinsmon (employee of owner) or (~~owner of well~~)
of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) J. Corry Tinsmon
1030, 200 W. Douglas, Wichita, KS
(Address)

SUBSCRIBED AND SWORN TO before me this 26th day of August, 19 76



Pamela S. Berg
Pamela S. Berg Notary Public.

My commission expires August 6, 1980

15-101-20183-0000

GABBERT-JONES, INC.
WICHITA, KANSAS
DRILLERS' WELL LOG

RECEIVED
STATE CORPORATION COMMISSION

AUG 27 1976

CONSERVATION DIVISION
Wichita, Kansas

08-27-1976

Munsell #1
C-SE-SE Sec 5-17S-29W
Lane County Kansas

Commenced: 6-20-76

Completed: 7-3-76

OPERATOR: TOMLINSON OIL CO., INC.

From	Depth to	Formation	Remarks
0	340	Surface Clay-Sand	Ran 8 jts of 8 5/8" csg
340	1043	Shale	set @ 336' Cemented w/
1043	1110	Sand	225 sks Common 2% Gel
1110	1700	Sand-Shale	3% CC PD @ 3:15 p.m.
1700	1760	Shale	6-20-76
1760	2015	Sand	
2015	2140	Shale-Redbed	
2140	2575	Shale	
2575	2970	Shale-Lime	
2970	3695	Lime-Shale	
3695	4580	Lime	
	4580 - TD		DRY & ABANDONED

STATE OF KANSAS)
) SS
COUNTY OF SEDGWICK)

I, the undersigned, being duly sworn on oath, state that the above Drillers Log is true and correct to the best of my knowledge and belief and according to the records of this office.

GABBERT-JONES, INC.

James S. Sutton II
JAMES S. SUTTON II

Subscribed and sworn to before me this 15th day of July, 1976.

Elizabeth J. Edwards
ELIZABETH J. EDWARDS-NOTARY PUBLIC

My Commission expires February 6, 1976.

