

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

Saline County, Sec. 29 Twp. 16 Rge. 1 ~~XX~~ (W)

Location as "NE/CNW/SW" or footage from lines SW NW SE

Lease Owner Capitt Drilling, Inc.

Lease Name Karber Well No. 1

Office Address 814 Union Center, Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed April 1 19 59

Application for plugging filed May 18 19 59

Application for plugging approved May 18 19 59


Plugging commenced May 18 19 59

Plugging completed May 21 19 59

Reason for abandonment of well or producing formation no oil in commercial quantities found

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well Mr. Toman

Producing formation Depth to top Bottom Total Depth of Well 2698 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	201'	none
				4-1/2"	2697'	2293'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled back to 2640'. Dumped 3 sacks of cement. Shot pipe off at 2293'. Pulled pipe and mudded hole to 200'. Set rock bridge and dumped 20 sacks of cement. Finished mudding to 30'. Set rock bridge and dumped 10 sacks in top of surface.

RECEIVED  
STATE CORPORATION COMMISSION  
MAY 28 1959  
CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Bert Self  
Address R. R. #4, Hutchinson, Kansas

STATE OF Kansas COUNTY OF Sedgwick, ss.

R. R. McNicol (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) R. R. McNicol  
814 Union Center, Wichita, Kansas  
(Address)

SUBSCRIBED AND SWORN TO before me this 27th day of May, 19 59.

My commission expires Sept. 30, 1959

Darlene May  
Darlene May Notary Public.

PLUGGING  
FILE SEC 29 T. 16 R. 1 W  
BOOK PAGE 41 L. 3

15-169-00111-0000

ROTARY DRILLING LOG

OPERATOR: Capitt Drilling, Inc.  
Karber No. 1  
SW NW SE Sec. 29-16S-1W,  
Saline County, Kansas

CONTRACTOR: Capitt Drilling, Inc.  
COMM: 3/22/59  
COMP: 4/1/59

Remarks: Set 8-5/8" surface casing  
at 202' cemented with 125  
sacks cement, 2% C.C.

Formations:

Surface hole	202'
Lime & Shale	331'
Lime & Shale Streaks	685'
Lime & Shale	740'
Shale & Lime	865'
Lime & Shale	980'
Shale & Shells	1250'
Shale & Lime Streaks	1556'
Shale & Lime	1600'
Lime	1630'
Shale	1670'
Lime & Shale	1715'
Lime	1900'
Lime & Shale	2033'
Lime	2440'
Shale & Lime	2500'
Lime & Shale	2558'
Shale	2570'
Shale & Lime	2648'
Chert	2698'
Rotary Total Depth	2698'

RECEIVED  
STATE CORRELATION COMMISSION  
MAY 28 1959  
CONSERVATION DIVISION  
Wichita, Kansas

Set 4-1/2" casing at 2697' cemented  
with 80 sacks regular cement.

We certify the above log is true and  
correct to the best of our knowledge  
and belief.

CAPITT DRILLING, INC.

*R.R. McNicol*

R. R. McNicol

PLUGGING  
FILE SEC. 29 T. 16 R. 14  
BOOK PAGE 41 LINE 3