


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Biting Building
Wichita, Kansas

NORTH



Locate well correctly on above
Section Flat

Saline County. Sec. 29 Twp. 16 Rge. (E) 1 (W)
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines C NW NE
Lease Owner The Bay Petroleum Corporation
Lease Name Karber 'B' Well No. 1
Office Address Box 513, Chase Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Oil well
Date well completed Jan. 24 19 44
Application for plugging filed Oct. 2 19 51
Application for plugging approved Oct. 4 19 51
Plugging commenced Oct. 2 19 51
Plugging completed Oct. 9 19 51
Reason for abandonment of well or producing formation Failure to produce in
in commercial quantity
If a producing well is abandoned, date of last production Sept. 16, 19 51
Was permission obtained from the Conservation Division or its agents before plugging was com-
menced? Yes

Name of Conservation Agent who supervised plugging of this well Mr. Rual Durkee
Producing formation Chat Depth to top 2618 Bottom 2624 Total Depth of Well 2624 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
				8 5/8"	145'	none
				5 1/2"	2618'	2035'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Ran river gravel and 5 sacks cement to bottom of hole;
Mudded hole and set bridge at 140';
Ran 15 sacks cement;
Mudded hole and ran 5 sacks cement to base of cellar.

RECEIVED
STATE CORPORATION COMMISSION
OCT 17 1951
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to The Bay Petroleum Corporation
Address Box 513, Chase Kansas

STATE OF Kansas, COUNTY OF Rice, ss.
Glen E. Armour (employee of owner ~~THE BAY PETROLEUM CORPORATION~~) of the above-described well,

being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God

(Signature) Glen E. Armour

(Address)

SUBSCRIBED AND SWORN to before me this 12 day of October, 19 51

My commission expires May 20, 1954
Vincent O. Gray Notary Public.

28-5091-s 8-50-10M

PLUGGING
FILE SEC 29 T 16 R 16
BOOK PAGE 114 LINE 11

15-169-00900-0000

Chase


WELL LOG BUREAU KANSAS GEOLOGICAL SOCIETY
412 Union National Bk. Bldg., Wichita, Kansas

Company - RAY PETRO. CORP.
Farm - Karber "B" No. 1.

SEC. 29 T. 16 R. 1 W
Cen NW NE

Total Depth. 2624 1/2'
Comm. 12-30-43 Comp. 3-11-44
Shot or Treated.
Contractor.
Issued. 3-25-44

County. Saline
KANSAS



CASING:
8 5/8" 145'
5" 2620 1/2'

Elevation. _____

Production. Pot. 312 B.

Figures Indicate Bottom of Formations.

surface clay	30
sand	45
shale & shells	137
lime	170
shale & lime	335
lime	445
shale & shells	490
lime, shale strks	540
lime & shale	810
shale & shells	1005
shale, lime strks	1185
lime & shale	1730
lime	1790
shale, lime strks	1950
shale	1985
lime & shale	2075
lime	2125
lime brkn	2195
lime & shale	2620
lime	2624 1/2'
Total Depth.	

Tops: Lansing 2000
Miss. 2620

150' OIH
500 Acid
Swb 5 to 6 BOPH, no wtr

RECEIVED
STATE CORPORATION COMMISSION

OCT 19 1951

CONSERVATION DIVISION
P. WIGGINS
FILE SEC 29 T 16 R 1 W
BOOK PAGE 114 LINE 11