

API NUMBER 15-101-21,177-A

LEASE NAME Delmar Whiting

WELL NUMBER #1

330 Ft. from S Section Line

1650 Ft. from E Section Line

SEC. 31 TWP. 18S RGE. 30 (E) or (W)

COUNTY Lane

Date Well Completed 11/15/87

Plugging Commenced 1/16/88

Plugging Completed 1/22/88

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

LEASE OPERATOR MAREXCO

ADDRESS P. O. Box 706, Edmond, OK 73083-0706

PHONE # 405) 340-6387 OPERATORS LICENSE NO. 9152

Character of Well OWWO - P & A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 1-15-16 (date)

by Richard Lacey, Dodge City, Kansas (KCC District Agent's Name).

Is ACO-1 filed? yes If not, is well log attached? yes

Producing Formation Fort Scott Depth to Top 4490' Bottom 4492 T.D. 4540'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
Fort Scott	non-commercial	4490	92	4-1/2"	4540'	2624'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set. Pump bottom plug with 20 sx cement (Portland) and 1 sack cottonseed hulls from 4540' to 4298'; shot pipe at 2624' pipe came loose and pulled to 2100', pumped 40 sx cement (portland) from 2100 to 2000', pulled pipe to 1300' and pumped 80 sx cement (Portland) from 1,300' to 1,100', pulled pipe to 240' and pumped 40 sacks cement (Portland) at 240' to 140', pulled pipe to 40' and pumped 10 sx cement (Portland) at 40' to 0'. Filled rat hole with 10 sx. (If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Sargent's Casing Pulling Service License No. 6547'

Address Box 506, Liberal, KS 67901

STATE OF Kansas COUNTY OF Seward, ss.

Stephen W. Marden (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Stephen W. Marden

(Address) P. O. Box 706, Edmond, OK 73083-0706

RECEIVED
 STATE CORPORATION COMMISSION
 SUBSCRIBED AND SWORN TO before me this 31st day of March, 19 88
4-1-88

APR - 1 1988
 My Commission Expires: April 29, 1989
 Notary Public

OWWC

GREAT GUNS

Sonic Cement

Bond Log

15-101-21177-0001

177-A

... East
p. 18, S. Rg. 30... West
..... Ft. from South Line of Section
..... Ft. from East Line of Section
(on Plat on reverse side)

FILING NO.	COMPANY	MAREXCO	
	WELL	Whiting #1	
	FIELD	N/A	
	COUNTY	Lane	STATE Kansas
	Location	SE-SW-SE	
	Sec	31	Twp 18 S Rge 30 W
Permanent Datum	Ground Level	Elev. 2899	Elev: K.B. 2904
Log Measured From	Kelly Bushing	5 Ft. Above Perm Datum	D.F. N/A
Drilling Measured From	Kelly Bushing		G.L. 2899

..... 330 feet
 Well # 1
 2899 feet MSL
 yes no
 yes no
 by set 1-2-1
 250' 100'
 1300' 1500'
 7' already set
 4640 feet
 Cippian

 7' feet per Alt. 2

Run No	One		
Date & Time Survey	11-7-87		
Date & Time Cementing	N/A		
Type Cementing Operation	Primary		
Depth Driller	4640		
Depth Logger	4540		
Logged Interval	4537	to	3750
Casing Driller	8 5/8"	@	216
Float Collar—D.V. Tool			
Squeeze Depth			
Amount & Type Cement	130 SKS B.J. Sure-Fill		
Amount & Type Admix	N/A		
Type Fluid in Hole	Water		
Fluid Level	Surface		
Salinity PPM Cl			
Weight lb/gal—Vis			
Approx. Logged Cem. Top	3920		
Calculated Cement Top			
Max Hole Temperature			
Tool No			
Spacing Recorded	Four		
Equipment—Location	44	G.B.	
Recorded by	T. Gutierrez		
Witnessed by	Mr. Evers		

RECEIVED
 NOV 30 1987
 STATE CORPORATION COMMISSION
 WICHITA, KANSAS

sted at the

RECEIVED
 STATE CORPORATION COMMISSION
 NOV 30 1987
 CONSERVATION DIVISION
 Wichita, Kansas

It water.

compression cement in the production pipe from below any usable water to surface within 120 days of spud date.

- 11. Call District office after well is either plugged or production casing is cemented in.