

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-171-20,100-0000

LEASE NAME TPL

WELL NUMBER 1-20

3960' Ft. from S Section Line

3960' Ft. from E Section Line

SEC. 20 TWP. 18 RGE. 31 (E or W)

COUNTY Scott

Date Well Completed 11-3-1976

Plugging Commenced 5-1-1992

Plugging Completed 5-1-1992

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Unico Inc.

ADDRESS Box 69, Commerce City, CO 80022

PHONE# (316) 286-7233 OPERATORS LICENSE NO. 3857

Character of Well gas

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 4-27-92 (date)

by Richard Lacy (KCC District Agent's Name).

Is AC0-1 filed? yes If not, is well log attached? _____

Producing Formation Krider Depth to Top 2762' Bottom 2777' T.D. 2800'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
Surface				8 5/8"	376'	0'
Production				4 1/2"	2799'	0'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

Pump 2 Sk. hulls & 25 Sk. cement to 2500', pressured to 750 lbs. shot hole @ 1400'

Pumped 80 Sk. cement @ 1400' - Shot hole @ 350' and circulated 125 Sk. cement

350' to surface. Dug out cellar and cut off 8 5/8" and 4 1/2" and cap.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Midwest Casing Pulling Service License No. 6497


Address Box F, Sublette, Ks. 67877

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Unico Inc.

STATE OF KANSAS COUNTY OF HASKELL, ss.

I, Edgar J. Eves

(Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.



(Signature) [Signature]

(Address) Box F, Sublette, Ks. 67877

SUBSCRIBED AND SWORN TO before me this 4th day of May, 1992

Sondra L. Eves
Notary Public

My Commission Expires: 12-6-92


RECEIVED
STATE CORPORATION COMMISSION

DEC 19 1991

12-19-91

CONSERVATION DIVISION
Wichita, Kansas

STATE	KANSAS	3-2-26 HP	MAP NO.	S-T-R	20-185-31W	WO
OPER	CAR-REN, INC.			SPOT	C NW/4	INIT
	300 W. DOUGLAS, WICHITA, KS			CO	SCOTT	WOE
WELL	LTL 1-20			ELEV	2958KB, 2953GR	FIN
CONTR	SLAWSON DRLG					
FIELD	EXT/HUGOTON NE(CHASE)					
IP	IPF 300-540 MCFGPD, CHASE(KRIDER)					



2762-77, SIGW, API 15-171-20100 - 0000
 SPUD 10-6-76, 8-5/8"@ 376 w/275, Geol-Charlie King
 & Jim Dilts
 DST 1(KRI) 2740-89, op90, si120, GTS/4", Stab @
 542 MCFGPD on 2nd op, ISIP 530, FP 84-119,
 BHT 115
 RTD 2800, log, 4 1/2"@ 2799 w/100
 Perf(KRI) 2762-77, 1000 gal A, Rec load
 IPF 300-540 MCFGPD, CHASE(KRIDER) 2762-77, SIGW,
 COMPLETED 2-28-77

KB LOG TOPS:
 STONE CORRAL 2240 + 718
 B/STONE CORRAL 2301 + 657
 HERINGTON 2736 + 222
 KRIDER 2760 + 198
 KRIDER PORO 2766 + 192
 RTD 2800 + 158
 LTD 2801 + 157
 TD IN CHASE

COMP ISSUED 3-14-77

CHASE(KRIDER) - HUGOTON NE FIELD - EXTENSION

Petroleum Information Corporation
 Copyrighted 1977. Reproduction Prohibited

*Box 69
 Commerce City Co, 80022
 # 3857
 Action*