

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 COLORADO DERRY BUILDING
WICHITA, KANSAS 67202

WELL PLUGGING RECORD

API NUMBER 15-171-20255-0000

TYPE OR PRINT
PLEASE FILL OUT COMPLETELY
AND MAKE REQUIRED AFFIDAVIT.

LEASE NAME Snyder #2

WELL NUMBER _____

SPOT LOCATION W/2 NE SW

SEC. 24 TWP. 18s RGE. 31w (E) OR (W)

COUNTY Scott

DATE WELL COMPLETED _____

PLUGGING COMMENCED 9/29/83

PLUGGING COMPLETED 10/6/83

LEASE OPERATOR Sandlin Oil Corporation

ADDRESS 2300 Security Life Bldg. Denver, Colo. 80202

PHONE #() _____ OPERATORS LICENSE NO. _____

CHARACTER OF WELL _____
(OIL, GAS, D&A, SWD, INPUT, WATER SUPPLY WELL)

DID YOU NOTIFY THE KCC/KDHE JOINT DISTRICT OFFICE PRIOR TO PLUGGING THIS WELL? Yes

WHICH KCC/KDHE JOINT OFFICE DID YOU NOTIFY? Dodge City

IS ACG-1 FILED? _____ IF NOT, IS WELL LOG ATTACHED? _____

PRODUCING FORMATION _____ DEPTH TO TOP _____ BOTTOM T.D. 4636'

SHOW DEPTH AND THICKNESS OF ALL WATER, OIL AND GAS FORMATIONS.

OIL, GAS OR WATER RECORDS | CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	305'	none
				4 1/2"	4634'	1794'

DESCRIBE IN DETAIL THE MANNER IN WHICH THE WELL WAS PLUGGED, INDICATING WHERE THE MUD FLUID WAS PLACED AND THE METHOD OR METHODS USED IN INTRODUCING IT INTO THE HOLE. IF CEMENT OR OTHER PLUGS WERE USED STATE THE CHARACTER OF SAME AND DEPTH PLACED, FROM FEET TO FEET EACH SET.

Sanded bottom off to 4310' & dumped 4 sacks cement. Shot pipe at 3526', 2826', 2538', 2036', 1920', & 1800'. Pulled 52 joints. Plugged well with 3 hulls, 20 gel, 50 cement, 20 gel, 1 hull, plug, & 170 sacks 60/40 poz 2% gel 3% c.c. Plugging complete.

(IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)

NAME OF PLUGGING CONTRACTOR Kelso Casing Pulling LICENSE NO. 6050
ADDRESS Box 347, Chase, Ks. 67524

STATE OF Kansas COUNTY OF Rice, SS.

R. Darrell Kelso (EMPLOYEE OF OPERATOR) OR (OPERATOR) OF ABOVE-DESCRIBED WELL, BEING FIRST DULY SWORN ON OATH, SAYS: THAT I HAVE KNOWLEDGE OF THE FACTS, STATEMENTS, AND MATTERS HEREIN CONTAINED AND THE LOG OF THE ABOVE-DESCRIBED WELL AS FILED THAT THE SAME ARE TRUE AND CORRECT, SO HELP ME GOD.

(SIGNATURE) R. Darrell Kelso

(ADDRESS) Box 347, Chase, Ks. 67524

SUBSCRIBED AND SWORN TO BEFORE ME THIS 11 DAY OF October, 1983

Irene Hoover
NOTARY PUBLIC



MY COMMISSION EXPIRES: _____

RECEIVED
STATE CORPORATION COMMISSION

FORM CP-4
REVISED 06-83

OCT 12 1983
16-12-83
CONSERVATION DIVISION
Wichita, Kansas

15-171-20255-0000

KELSO CASING PULLING



Post Office Box 176

CHASE, KANSAS 67524

Phone 938-2457

DARRELL KELSO — Owner

Customer's
Order No.
& Date

Refer To
Invoice No. 3322

SOLD TO Sandlin Oil Corporation
2300 Security Life Bldg.
Denver, Colo. 80202

Invoice Date 10/11/83

Lease and Well No. Snyder #2 Scott County

TERMS: All purchases made on credit during the month are due and payable by the 10th of the following month. Any balance not paid by the 24th of the following month shall be subject to a FINANCE CHARGE computed at a periodic rate of 1% per month which is an ANNUAL PERCENTAGE RATE of 12%.

QUANTITY	DESCRIPTION	UNIT PRICE	AMOUNT
	Move in Charge		600.00
	100 mile move from Chase		100.00
1794'	4 1/2" casing @ .60¢	52 joints	1076.40
6	Shots @ \$75.00 ea.		450.00
	Sand		10.00
4	Nights expense for 2 men @ \$35.00 ea.		280.00
			<u>2516.40</u>
	Sales Tax on \$1536.40		61.45
	Balance Due;		<u>\$ 2577.85</u>

- 9/29/83 Moved in, raised pole. Used truck to move tubing back. Set junk rack in, dug cellar.
- 9/30/83 Set floor in. Could not get water line from well run.
- 10/3/83 Still waiting on water line to be run. Worked on rig.
- 10/4/83 Sanded bottom off to 4310' & dumped 4 sacks cement. Shot and worked pipe at 3526', 2826', 2538', 2036', 1920'. Left on tension.
- 10/5/83 Shot at 1800', came free. Pulled 52 joints. Tore floor down. cleaned up location, tallied pipe.
- 10/6/83 Plugged well with 3 hulls, 20 gel, 50 cement, 20 gel, 1 hull, plug, & 170 sacks 60/40 poz 2% g;e 3% c.c.
Plugging complete.