

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-101-21,490-0000

LEASE NAME Horton

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

WELL NUMBER 1

4620 Ft. from S Section Line

1980 Ft. from E Section Line

LEASE OPERATOR A. L. Abercrombie, Inc.

SEC. 30 TWP. 19S RGE. 27E COR. 1 (W)

ADDRESS 801 Union Center, Wichita, KS 67202

COUNTY Lane

PHONE#(316) 262-1841 OPERATORS LICENSE NO. 539 **RECEIVED**
STATE CORPORATION COMMISSION

Character of Well good

Plugging Commenced 10-10-88

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

OCT 31 1988
10-31-88

Plugging Completed 10-10-88

The plugging proposal was approved on 10-10-88 (date)

by State Pluggers, Steve Durant and Dan Goodrow (KCC District Agent's Name).

CONSERVATION DIVISION
Wichita, Kansas

Is ACO-1 filled? Yes If not, Is well log attached? _____

Producing Formation _____ Depth to Top _____ Bottom _____ T.D. 4665'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8 5/8"	234'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

Circulate heavy mud. 1st plug from 2074' to 1874' w/50 sx. 2nd plug from 1150' to 830' w/80 sx. 3rd plug from 600' to 440' w/40 sx. 4th plug from 260' to 100' w/40 sx. 5th plug from 40' to surface w/10 sx. Rathole-15 sx. All cement 60/40 posmix, 6% gel.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Abercrombie Drilling, Inc. License No. 5422

Address 801 Union Center, Wichita, KS 67202

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: A. L. Abercrombie, Inc.

STATE OF Kansas COUNTY OF Sedgwick, ss.

Jack K. Wharton (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.


(Signature) Jack K. Wharton

(Address) 801 Union Center
Wichita, KS 67202

SUBSCRIBED AND SWORN TO before me this 27th day of October, 1988

Jo Ann M. Walker
Notary Public

Commission Expires: 10/24/90



NOTICE OF INTENTION TO DRILL

(see rules on reverse side)

Expected Spud Date: 10 01 88
month day year

API Number 15-101-21,490-0000

OPERATOR: License # 5393
Name A. L. Abercrombie, Inc.
Address 801 Union Center
City/State/Zip Wichita, KS 67202
Contact Person Jack L. Partridge
Phone (316) 262-1841

C NW NE Sec. 30 Twp. 19 S. Rg. 27 East
4620 FSL Ft. from South Line of Section
1980 FEL Ft. from East Line of Section

(Note: Locate well on Section Plat on reverse side)

Nearest lease or unit boundary line 660 feet
County Lane

Lease Name Horton Well # 1
Ground surface elevation feet MSL

Domestic well within 330 feet: yes X no
Municipal well within one mile: yes X no

Depth to bottom of fresh water 100'
Depth to bottom of usable water 1000'

Surface pipe by Alternate: 1 2 X

Surface pipe planned to be set 220'

Conductor pipe required None

Projected Total Depth 4650 feet

Formation Miss

CONTRACTOR: License # 5422
Name Abercrombie Drilling, Inc.
City/State Wichita, KS 67202

Well Drilled For: Well Class: Type Equipment:
X Oil Storage Infield X Mud Rotary
Gas Inj Pool Ext Air Rotary
OWWO Expl X Wildcat Cable

If OWWO: old well info as follows:

Operator
Well Name
Comp Date Old Total Depth

I certify that well will comply with K.S.A. 55-101, et seq., plus eventually plugging hole to K.C.C. specifications.

Date 9-26-88 Signature of Operator or Agent Paul L. Partridge Title Vice Pres.

For KCC Use:

Conductor Pipe Required feet; Minimum Surface Pipe Required 200 feet per Alt. X (2)

This Authorization Expires 3-26-89 Approved By LKM 9-26-88

EFFECTIVE DATE: 10-1-88

set 220+ of 85/8 on 10-1-88

C NW NE Sec. 30 Twp. 19 S. Rg. 27 East

PLUGGING PROPOSAL IF ABOVE IS D & A

This plugging proposal will be reviewed and approved or revised at the time the district office is called prior to setting surface casing (call 7 a.m. to 5 p.m. workdays).

1st plug @ ft. deep	Base Anhydrite	or formation with	50 sx	feet of	60/40 pos, 6% gel
2nd plug @ ft. deep	Chey-Dakota	or formation with	80 sx	feet of	60/40 pos, 6% gel
3rd plug @ ft. deep	250'	or formation with	50 sx	feet of	60/40 pos, 6% gel
4th plug @ ft. deep	40'	or formation with	10 sx	feet of	60/40 pos, 6% gel
5th plug @ ft. deep		or formation with		feet of	
(2) Rathole to surface minus 5 feet 15 sx of 60/40 pos, 6% gel				(b) Mousehole to surface minus 5 feet	

PUSHER	FORMATION	ANHYDRITE	STARTING TIME & DATE	COMPLETION TIME & DATE	1st PLUG @	FT. W/	SX
TD					2nd PLUG @	FT. W/	SX
SURFACE PIPE @					3rd PLUG @	FT. W/	SX
					4th PLUG @	FT. W/	SX
					RAT HOLE CIRCULATED W/		SX
					MOUSE HOLE CIRCULATED W/		SX
					WATER WELL PLUGGED W/		SX
					CEMENT COMPANY		
					TECHNICIAN		

RECEIVED
STATE CORPORATION COMMISSION
OCT 13 1988
10-18-88
CONSERVATION DIVISION
Wichita, Kansas