

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-02-3-117

API NUMBER 15-101-21731-000

LEASE NAME West-32C

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

WELL NUMBER 1

990' Ft. from ^N Section Line

330' Ft. from E Section Line

LEASE OPERATOR Ritchie Exploration, Inc.

SEC. 32 TWP. 19 SRGE. 34 ~~NE~~ (W)

ADDRESS 125 N. Market - Suite 1000
Wichita, KS 67202

COUNTY Lane

PHONE# (316) 267-4375 OPERATORS LICENSE NO. 4767

Date Well Completed 11-27-96

Character of Well D&A

Plugging Commenced 11-27-96

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 11-27-96

The plugging proposal was approved on November 27, 1996 (date)

by Steve Pfeifer (KCC District Agent's Name).

Is ACO-1 filed? Yes If not, is well log attached? Yes

Producing Formation _____ Depth to Top _____ Bottom _____ T.D. 4600'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8 5/8"	212'	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.
Spotted 50 sx. cement at 2022' thru drill pipe. Spotted 80 sx. cement at 1200' thru drill pipe. Spotted 50 sx. cement at 600' thru drill pipe. Spotted 40 sx. cement at 240' thru drill pipe. Spotted 10 sx. cement at 40' thru drill pipe. Spotted 15 sx. cement in rathole.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor White & Ellis Drilling, Inc. License No. 5420

Address P. O. Box 48848, Wichita, KS 67201-8848

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Ritchie Exploration, Inc.

STATE OF KANSAS COUNTY OF SEDGWICK, ss.

Michael L. Considine (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Michael L. Considine

(Address) P. O. Box 48848
Wichita, KS 67201-8848

CAROLYN J. ZADEN
NOTARY PUBLIC
STATE OF KANSAS
My Appt. Exp. 9-5-2000
SUBSCRIBED AND SWORN TO before me this 2nd day of December, 19 96
Carolyn J. Zaden
Notary Public

My Commission Expires: September 5, 2000

FOR KCC USE:

EFFECTIVE DATE: 10-27-96

DISTRICT # 1

SEAL Yes X No

State of Kansas

101-21,731-6000

NOTICE OF INTENTION TO DRILL

FORM C-1 7/9 FORM MUST BE TYPE ALL BLANKS MUST BE FILLED

Must be approved by the K.C.C. five (5) days prior to commencing well

Expected Spud Date 10 31 96 month day year

Spot NW SW SW Sec 32 Twp 19 S. Rg 27W East West

OPERATOR: License # 4767 Name: Ritchie Exploration, Inc. Address: 125 N. Market, Suite 1000 City/State/Zip: Wichita, KS 67202 Contact Person: Rocky Milford Phone: (316) 267-4375

990 feet from South (North) line of Section 330 feet from East West line of Section IS SECTION X REGULAR (IRREGULAR?)

(NOTE: Locate well on the Section Plat on Reverse Side County: Lane

Lease Name: West-32C Well #: 1 Field Name: Wildcat

Is this a Prestrat/Spaced Field? yes X no Target Formation(s): L/KC. Miss

Nearest Lease or unit boundary: 330 Ground Surface Elevation: 2680 est feet MSI

Water well within one-quarter mile: yes X no Public water supply well within one mile: yes X no

Depth to bottom of fresh water: 180 Depth to bottom of usable water: 1140

Surface Pipe by Alternata: 1 X 200 Length of Surface Pipe Planned to be set: 200

Length of Conductor pipe required: Projected Total Depth: 4650

Formation at Total Depth: Miss Water Source for Drilling Operations: well farm pond X other

DNR Permit #: Will Cores Be Taken?: yes X no

If yes, proposed zone: 200' Alt. II Req.

CONTRACTOR: License #: 5420 Name: White & Ellis

Well Drilled For: Well Class: Type Equipment: X Oil Enh Rec Infield Mud Rotary Gas Storage Pool Ext. Air Rotary OWD Disposal Wildcat Cable Seismic # of Holes Other

If OWD: old well information as follows: Operator: Well Name: Comp. Date: Old Total Depth

Directional, Deviated or Horizontal wellbore? yes X no If yes, true vertical depth: Bottom Hole Location:

Exp. 4/22/97

AFFIDAVIT

200' Alt. II Req.

The undersigned hereby affirms that the drilling, completion and eventual plugging of this well will comply with 101, et. seq.

Pusher Judy SPUD DATE 11-19-96 INIT. R.L.

LENGTH SURFACE PLANNED 200 I RESERVE PIT STATUS- REMOVE FLUID LINED after salt sect. bbls. when done bbls.

RATHOLED AHEAD? Y N SIZE HOLE SURFACE PIPE 8 5/8 @ 2 1/2 CONDUCTOR ANHYDRITE T-1985 B-2022 ELEVATION 2245 FORMATION 1600

RAN PIPE @ DV TOOL ALT II DONE SX Y N Ar buckle Plug @ Ft. W/ SX

Dug./Council @ Ft. W/ SX 1 Anhydrite Base @ 2022 Ft. W/ 50 SX

1/2 Base Anyh. @ 1200 Ft. W/ 80 SX 1/2, 1/2 Plug @ 600 Ft. W/ 50 SX

Bottom Surface @ 240 Ft. W/ 40 SX 40' Plug @ 40 Ft. W/ 10 SX

RAT HOLE CIRC/W 15 SX MOUSE HOLE W/ SX WATER WELL SX (Irr. Well Pond) Hauling

TECHNICIAN SP DATE 11-21-96 TYPE OF CEMENT 60/40 @ 26 1/2 gal 1/4 15 sand

STARTING TIME 3:59 (APM) DATE 11-27-96 COMPLETION TIME 6:45 (AMP) DATE 11-27-96 CEMENT COMPANY Alca

12-296