

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-171-20.290-0000

LEASE NAME Ruby Eitel

WELL NUMBER #1

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

4620 Ft. from S Section Line

4180 Ft. from E Section Line

SEC. 25 TWP. 18 RGE. 31 (E) or (W)

COUNTY Scott

LEASE OPERATOR Sandlin Oil Corporation

ADDRESS 2300 Security Life Building Denver, CO.

PHONE# (303) 623-5055 OPERATORS LICENSE NO. 6677

Date Well Completed 3-8-85

Character of Well D & A

Plugging Commenced 9:00 Pm 7th

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 12:45 AM 8th

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? District #1 Dodge City, KS.

Is ACO-1 filed? yes if not, is well log attached? yes

Producing Formation _____ Depth to Top _____ Bottom T.D. 4630

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
Surface hole	Sand & Shale	0	304	8 5/8	296	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.
Plug @ 2200'/50 sx, plug @ 1460'/50 sx, plug @ 350'/750 sx, plug @ 40'/10 sx
Rathole/15 sx 175 sx 60/40 pozmix, 2% gel, 3% cc.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor DNB Drilling, Inc. License No. 5476

Address 535 N. Oliver Wichita, KS 67208

STATE OF Colorado COUNTY OF Denver, ss.

MAR 21 1985
3-21-85

Gary Sandlin - Sandlin Oil Corp. (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) [Signature]
2300 Security Life Bldg.
(Address) Denver, CO 80202

SUBSCRIBED AND SWORN TO before me this 18th day of March, 19 85

[Signature]
Notary Public

My Commission Expires: 6-30-87

D N B Drilling, Inc.

ROTARY CONTRACTOR DRILLING DEALS

J. L. DONELSON, PRES.
(316) 687-5471

535 NORTH OLIVER

WICHITA, KANSAS 67208

DRILLERS' LOG

Sandlin Oil Corporation
2300 Security Life Building
Denver, CO. 80202

#1 Ruby Eitel
1100' WL, 660' NL
Sec. 25-T18S-R31W
Scott County, KS.

Commenced: 2-27-85
Completed: 3-8-85

Surface casing: Ran 7 jts. 8 5/8", 23# new casing; tallied 295.81,
set @ 304', cmt. w/200 sx 60/40 pozmix, 2% gel,
3% cc. Cement did circulate. Plug down @ 10:45 PM.

FORMATION

Sand & Shale
Shale
Anhydrite
Shale
Shale & Lime
Lime

DEPTH

0-2345
2345-2603
2604-2630
2630-2970
2970-3920
3920-4630

I do hereby certify that the foregoing statements are true and correct to the best of my knowledge and belief.

DNB Drilling, Inc.


By 

STATE OF KANSAS
NOTARY PUBLIC


MAR 21 1985
3-21-85

STATE OF KANSAS: ss:

Subscribed and sworn to before me this 13th day of March, 1985.



Gwen Hinderliter, Notary Public



My appointment expires:
January 11, 1988