

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15171-300650000

LEASE NAME Stienberg #1-26

WELL NUMBER _____

SPOT LOCATION C NE NE SW

SEC. 26 TWP. 18 RGE. 31 (E) or

COUNTY Scott

Date Well Completed _____

Plugging Commenced 4/19/84

Plugging Completed 5/17/84

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Cargill Natural Gas Operations bought by Kelso
Casing Pulling
ADDRESS 604 One Main Place, Wichita, Ks. 67202

PHONE # () _____ OPERATORS LICENSE NO. _____

Character of Well _____
(Oil, Gas, D&A, SMD, Input, Water Supply Well)

Did you notify the KCC/KDNE Joint District Office prior to plugging this well? Yes

Which KCC/KDNE Joint Office did you notify? Dodge City

Is ACO-1 filed? _____ if not, is well log attached? _____

Producing formation _____ Depth to top _____ bottom _____ T.D. 2800'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8.5/8	250'	none
				4"	2800'	816.64'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole, if cement or other plugs were used state, the character of same and depth placed, from _____ feet to _____ feet each set.

Plugged bottom with sand to 2700' & ran 4 sacks cement. Shot pipe at 1513', 1009', 926', 813'. Pulled 25 joints of pipe. Plugged well with 2 hulls, 10 gel, 50 cement, 10 gel, 1 hull, plug, & 225 sacks 50/50 poz 2% gel 3% c.c.

Plugging complete

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Kelso Casing Pulling License No. 6050
Address Box 347, Chase, Ks. 67524

STATE OF Kansas COUNTY OF Rice, ss.

Mike Kelso (employee of operator) or (operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Mike Kelso

(Address) Box 347, Chase, Ks. 67524

SUBSCRIBED AND SWORN TO before me this 22nd day of May, 1984


IRENE HOOVER
State of Kansas
My Comm. Exp. Aug. 15, 1985

Irene Hoover
NOTARY PUBLIC

My Commission expires.

RECEIVED
STATE CORPORATION COMMISSION
MAY 23 1984
5-23-84
CONSERVATION DIVISION
Wichita, Kansas

15-171-30065-0000



8-72W Map No
OPEF KATEX OIL CO.
BORGER, TEXAS
WELL #1 STEINBERG
CONTR MURFIN DRLG. CO.
W/ UNNAMED DISCOVERY
GA 1,000,000 CFGPD, SIP 410#
KRI 2747 1/2 - 48 1/2



26-18S-31W
C NE NE SW
SCOTT (KS)
2927 KB

B/CM ANH 2264 +654
HOLL 2702 +216
HERR 2713 +205
KRI 2742 +176
B/KRI 2769 +149
WINF 2791 +127
LTD 2802 +116
RTD 2800 +118

SPD 6-28-66 8-5/8" @250/100 SX BILL ATKINSON, GEOL

NO DST'S - RTD 2800' - SCHLUMBERGER LOG - 4 1/2" @2800/100 SX
MCT, CO, PF 4-2747 1/2 - 48 1/2 (KRI)
500A, 8 SG, SIP 410#/6 DAYS, FRAC 2000 GAL (3%)
A + 2000#SD + 22 TONS CO₂ & FLUSH W/50 BW, GA 887,000 CFG
PD (WET) GA APPROX 1,000,000 CFGPD
GA 1,000,000 CFGPD, SIP 410# (KRI 2747 1/2 - 48 1/2)

COMPLETED 8-9-66 (UNNAMED DISCOVERY) (NOTE: HELIUM CONTENT NOT CHECKED)

(i See

2827
8427
4179

MISCEL DATA
GEOLOGICAL BILL ATKINSON ELEV 2924 DF SPUD DATE 6-28-66
FTG 2918 GR DRLG COMP
SUPPT FR BY DATA 6-27-66
CSG 8" 250 W/100 SX. 4 1/2" 2800 W/100 SX. COMP 8-11-66